

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	•	LIVINGSTON	354	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
•(123)123XRS-3, (124)RS-5, (123)BR-3				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED/20% ST.		VILLAGE OF FORREST				
				MAINLINE ROADWAY 1000-2A F	STRUCTURE SN 053-0179 X081-2A BRF	SFTY-2A/SN 053-2027 F	NEW SIDEWALKS 50%STATE 50% FED.			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	963	963						
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	168	168						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	506	506						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36						
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	104930	104930						
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	11685	11685						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	676	676						
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6						
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	54	54						
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	156	156						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12						
	78300100 PAVEMENT MARKING REMOVAL	SO FT	2823	2823						
	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	632	632						
	X0323265 REMOVE EXISTING RIPRAP	SO YD	111	111						
	X0323988 TEMPORARY SOIL RETENTION SYSTEM	SO FT	425	425						
* X0324762	WIDELoad DETOUR SIGNING	L SUM	1	1						
	X0976500 END SECTIONS TO BE REMOVED	EACH	19	19						
	X5020501 UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1					
	X5020502 UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1					
	Z0001900 ASBESTOS BEARING PAD REMOVAL	EACH	96		96					
+ Z0005300	BOX CULVERTS TO BE CLEANED	EACH	5	5						
+ Z0010555	DITCH CLEANING	FOOT	120	120						
	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1						
+ Z0014700	CULVERT TO BE CLEANED	EACH	2	2						
	Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	8						
	Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	8						
	Z0032900 LAND SECTION MARKERS	EACH	21	21						
■ Z0076000	TRAINEES	HOOR	2,000	2,000						
XX005374	PIPE UNDERDRAINS 6" (MODIFIED)	FOOT	305	305						
* 56100600	WATER MAIN 6"	FOOT	742	742						
* 56100800	WATER MAIN 10"	FOOT	180	180						
* 56104900	WATER VALVES 6"	EACH	1	1						
* 56105100	WATER VALVES 10"	EACH	1	1						
* 56200300	WATER SERVICE LINE 1"	FOOT	150	150						
* 56201400	CORPORATION STOPS 1"	EACH	10	10						
* 56400600	FIRE HYDRANTS	EACH	2	2						
* 60900515	CONCRETE THRUST BLOCKS	EACH	12	12						

\$\$\$\$\$FILENAME\$\$\$\$\$DATE\$\$\$\$\$

LEGEND:
 * SPECIALTY ITEMS
 ■ Y080
 + NON-PARTICIPATING 100% STATE

REVISED BY IDOT

REVISIONS	
NAME	DATE
MJ	12-24-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 7 OF 7

SCALE: VERT. NONE
 HORIZ. NONE

DATE :
 DRAWN BY:
 CHECKED BY: