

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	•	LIVINGSTON	354	19
STA. TO STA.			TO STA.	
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
•(123,123)RS-3, (124)RS-5, (123)BR-3.				

ITEM NO. 44201843 CLASS D PATCHES, TYPE III, 16 INCH

LOCATION	DESCRIPTION	LENGTH (FOOT)	WIDTH (FOOT)	SQ. YD.
RT. STA. 775+14 TO STA. 775+26	PAVEMENT PATCH	12	12	16
LT. STA. 775+14 TO STA. 775+26	PAVEMENT PATCH	12	12	16
RT. STA. 852+42.5 TO STA. 852+57.5	PAVEMENT PATCH	15	12	20
LT. STA. 861+94 TO STA. 862+06	PAVEMENT PATCH	12	12	16
RT. STA. 870+94 TO STA. 871+06	PAVEMENT PATCH	12	12	16
RT. STA. 877+92.5 TO STA. 878+07.5	PAVEMENT PATCH	15	12	20
LT. STA. 877+94 TO STA. 878+06	PAVEMENT PATCH	12	12	16
RT. STA. 880+94 TO STA. 881+06	PAVEMENT PATCH	12	12	16
LT. STA. 880+94 TO STA. 881+06	PAVEMENT PATCH	12	12	16
RT. STA. 905+84 TO STA. 905+96	PIPE CULV. REM.	12	12	16
LT. STA. 905+84 TO STA. 905+96	PIPE CULV. REM.	12	12	16
LT. STA. 990+42.5 TO STA. 990+57.5	PAVEMENT PATCH	15	12	20
LT. STA. 1004+94 TO STA. 1005+06	PAVEMENT PATCH	12	12	16
LT. STA. 1054+92.5 TO STA. 1055+07.5	PAVEMENT PATCH	15	12	20
RT. STA. 1104+94 TO STA. 1105+06	PAVEMENT PATCH	12	12	16
RT. STA. 1127+92.5 TO STA. 1128+07.5	PAVEMENT PATCH	15	12	20
RT. STA. 1164+44 TO STA. 1164+56	PAVEMENT PATCH	12	12	16
LT. STA. 1164+44 TO STA. 1164+56	PAVEMENT PATCH	12	12	16
RT. STA. 1185+18 TO STA. 1185+30	PIPE CULV. REM.	12	12	16
LT. STA. 1185+18 TO STA. 1185+30	PIPE CULV. REM.	12	12	16
RT. STA. 1206+94 TO STA. 1207+06	PAVEMENT PATCH	12	12	16
RT. STA. 1257+22.5 TO STA. 1257+37.5	PAVEMENT PATCH	15	12	20
LT. STA. 1257+22.5 TO STA. 1257+37.5	PAVEMENT PATCH	15	12	20
TOTAL = 396				

ITEM NO. 44201845 CLASS D PATCHES, TYPE IV, 16 INCH

LOCATION	DESCRIPTION	LENGTH (FOOT)	WIDTH (FOOT)	SQ. YD.
RT. STA. 836+84 TO STA. 837+12	BOX CULV. REM.	28	12	37
LT. STA. 836+84 TO STA. 837+12	BOX CULV. REM.	28	12	37
RT. STA. 862+92 TO STA. 863+12	PIPE CULV. CONST.	20	12	27
LT. STA. 862+92 TO STA. 863+12	PIPE CULV. CONST.	20	12	27
RT. STA. 881+90 TO STA. 882+10	PAVEMENT PATCH	20	12	27
LT. STA. 881+90 TO STA. 882+10	PAVEMENT PATCH	20	12	27
RT. STA. 886+55 TO STA. 886+79	BOX CULV. REM.	24	12	32
LT. STA. 886+55 TO STA. 886+79	BOX CULV. REM.	24	12	32
RT. STA. 950+40 TO STA. 950+60	PAVEMENT PATCH	20	12	27
LT. STA. 950+40 TO STA. 950+60	PAVEMENT PATCH	20	12	27
RT. STA. 983+27.5 TO STA. 983+52.5	PAVEMENT PATCH	20	12	34
LT. STA. 983+27.5 TO STA. 983+52.5	PAVEMENT PATCH	20	12	34
RT. STA. 1082+94.5 TO STA. 1083+14.5	PIPE CULV. REM.	25	12	34
LT. STA. 1082+94.5 TO STA. 1083+14.5	PIPE CULV. REM.	25	12	34
RT. STA. 1192+87.5 TO STA. 1193+12.5	PAVEMENT PATCH	25	12	34
LT. STA. 1192+87.5 TO STA. 1193+12.5	PAVEMENT PATCH	25	12	34
RT. STA. 1215+92 TO STA. 1216+26	BOX CULV. REM.	34	12	45
LT. STA. 1215+92 TO STA. 1216+26	BOX CULV. REM.	34	12	45
RT. STA. 1227+59 TO STA. 1227+83	BOX CULV. REM.	24	12	32
LT. STA. 1227+59 TO STA. 1227+83	BOX CULV. REM.	24	12	32
RT. STA. 1245+69 TO STA. 1246+01	BOX CULV. REM.	32	11	39
LT. STA. 1245+69 TO STA. 1246+01	BOX CULV. REM.	32	19	68
TOTAL = 751				

ITEM NO. 44300900 STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A

LOCATION	FOOT
LT. STA. 1240+15 TO LT. STA. 1248+42	827
RT. STA. 1240+15 TO RT. STA. 1248+42	827
TOTAL = 1654	

ITEM NO. 48102100 AGGREGATE WEDGE SHOULDER, TYPE B

ITEM NO. 48203020 HOT-MIX ASPHALT SHOULDERS, 5 3/4"

LOCATION	(AGG. SHLD.) TON	(HMA SHLD.) SQ. YD.
STA. 767+72 TO STA. 804+70	317	2942
(SN. 053-0166)	---	----
STA. 804+70 TO STA. 810+47	15	741
STA. 810+47 TO STA. 863+42	357	6374
STA. 863+42 TO STA. 916+33	517	3831
STA. 916+33 TO STA. 949+25	273	2444
(SN. 053-0179)	---	----
STA. 949+25 TO STA. 970+04	167	1505
STA. 970+04 TO STA. 1023+57	518	3889
STA. 1023+57 TO STA. 1076+36	504	3825
STA. 1076+36 TO STA. 1129+35	515	3838
STA. 1129+35 TO STA. 1182+24	520	3830
STA. 1182+24 TO STA. 1235+18	506	3474
STA. 1235+18 TO STA. 1252+29	109	1436
STA. 1252+29 TO STA. 1273+30	---	----
TOTAL = 4318		38,129

ITEM NO. 50102600 CONCRETE REMOVAL

LOCATION	DESCRIPTION	EACH
40' LT. STA. 821+96	CONC. SLOPWALL	1
39' RT. STA. 886+67	WEIR	1
40' RT. STA. 1083+05	WEIR	1
40' RT. STA. 1130+02	WEIR	1
TOTAL = 4		

ITEM NO. 50105210 REMOVE EXISTING CULVERTS

LOCATION	SIZE	TYPE	FOOT	CULVERT NO.
Ⓢ STA. 836+98	4' x 3'	RCBC	41.5	⑤
Ⓢ STA. 886+65	3' x 2'	RCBC	51.6	⑦
Ⓢ STA. 1216+09	•10' x 4'	RCBC	42	⑪
Ⓢ STA. 1227+71	3' x 2'	RCBC	52.5	⑫
TOTAL = 187.6				

ITEM NO. 50105220 PIPE CULVERT REMOVAL

LOCATION	TYPE	SIZE (INCHES)	LENGTH (FEET)
769+10, RT.	CMP	15	45
777+45, RT.	CMP	15	26
781+25, RT.	CMP	15	26
782+95, RT.	CMP	15	6
784+10, LT.	RCP	15	34
792+10, RT.	CMP	15	26
797+00, LT.	CMP	24	24
797+46, RT.	CMP	18	28
800+25, LT.	CMP	24	38
821+86, LT.	CMP	30	32
858+88, LT.	CMP	24	30
858+90, RT.	CMP	15	26
863+39, RT.	VCP	15	42
863+40, LT.	VCP	15	42
864+73, RT.	CMP	15	26
875+63, RT.	CMP	15	28
905+90.5, CL	CMP	18	57
916+34, LT.	VCP	18	42
916+39, RT.	VCP	15	41
919+00, RT.	CMP	15	24
943+61, LT.	VCP	15	33
952+16, RT.	CMP	15	28
952+78, LT.	VCP	15	27
970+00, RT.	CMP	15	38
982+00, RT.	-	-	44
996+75, RT.	CMP	30	40
996+75, RT.	CMP	30	40
1000+87, LT.	CMP	24	24
1000+87, LT.	CMP	15	24
1010+09, LT.	CMP	30	26
1023+60, LT.	CMP	15	77.5
1023+60, RT.	CMP	15	38
1027+95, RT.	CMP	15	26
1032+92, LT.	CMP	15	26
1047+37, RT.	CMP	15	26
1050+05, LT.	CMP	15	26
1050+06, RT.	CMP	15	32
1053+39, LT.	CMP	18	50
1055+14, RT.	CMP	15	26
1056+77, LT.	CMP	15	26
1063+26, RT.	CMP	15	24
1083+04.5, LT.	CLAY	10	47
1083+04.5, CL	ELIP. CONC. PIPE	36	95
1083+04.5, RT.	RUBBER DRAIN	10	52
1089+73, RT.	CMP	15	30
1091+13, LT.	CMP	15	44
1098+87, LT.	CMP	15	26
1102+92, RT.	CMP	15	26
1114+37, LT.	CMP	15	52
1129+35, LT.	CMP	18	40
1129+35, RT.	CMP	18	40
1129+35, RT.	CMP	18	26
1144+70, RT.	CMP	15	26
1155+87, RT.	CMP	15	16
1173+66, RT.	CMP	18	48
1182+25, LT.	CMP	15	54
1185+24, CL	CMP	18	26
1189+78, RT.	CMP	15	26
1193+87, RT.	CMP	15	26
1205+18, LT.	CMP	15	26
1205+25, RT.	CMP	15	26
1208+82, RT.	CMP	15	26
1210+67, RT.	CMP	15	28
1216+09, LT.	CMP	12	30
1231+05, RT.	CMP	18	26
1234+93, LT.	CMP	12	44
1236+06, RT.	CMP	15	44
1235+20, LT.	CMP	12	44
1237+54, RT.	CMP	18	44
1238+40, LT.	CMP	15	8
1238+66, LT.	PLASTIC	15	15
1238+75, RT.	CORR. PLASTIC	15	48
1239+54, RT.	CONC.	15	68
1240+55, LT.	CMP	15	17
1241+00, RT.	CORR. PLASTIC	8	50
1242+77, LT.	CMP	15	48
1243+05, RT.	CMP	15	300
1245+90, RT.	CONC.	15	33
1246+38, RT.	CONC.	15	32
1247+10, RT.	CONC.	15	48
1247+75, RT.	CONC.	15	58
1248+53, RT.	CONC.	15	135
1248+50, LT.	CMP/VCP	15	58
1249+60, RT.	CONC.	15	26
1250+40, RT.	CMP	15	
TOTAL = 3352.5			

ITEM NO. 50800105 REINFORCEMENT BARS

LOCATION	POUND
LT. STA. 810+98.5	22
RT. STA. 810+98.5	22
LT. STA. 828+30	22
RT. STA. 828+30	22
TOTAL = 88	

ITEM NO. 51100100 SLOPEWALL 4 INCH

LOCATION	SQ. YD.
LT. STA. 821+95	14
TOTAL = 14	

ITEM NO. 54001001 BOX CULVERT END SECTION, CULVERT NO. 1

LOCATION	SIZE	EACH
LT. & RT. STA. 774+90	3' x 2'	2
TOTAL = 2		

ITEM NO. 54001002 BOX CULVERT END SECTION, CULVERT NO. 2

LOCATION	SIZE	EACH
RT. STA. 788+96	3' x 2'	1
TOTAL = 1		

ITEM NO. 54001003 BOX CULVERT END SECTION, CULVERT NO. 3

LOCATION	SIZE	EACH
LT. & RT. STA. 810+98.5	3' x 2'	2
TOTAL = 2		

ITEM NO. 54001004 BOX CULVERT END SECTION, CULVERT NO. 4

LOCATION	SIZE	EACH
LT. & RT. STA. 828+30	3' x 2'	2
TOTAL = 2		

ITEM NO. 54001005 BOX CULVERT END SECTION, CULVERT NO. 5

LOCATION	SIZE	EACH
LT. & RT. STA. 836+98	8' x 4'	2
TOTAL = 2		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
SCALE: VERT.	HORIZ.	DRAWN BY
DATE		CHECKED BY