

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326		LIVINGSTON	354	53
STA. 1040+00		TO STA. 1055+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		•(123)XRS-3,(124)RS-5,(123)BR-3		

**LEGEND**

- X - TREE REMOVAL
- ▨ - PAVEMENT REMOVAL & CLASS D PATCH
- - SPECIAL DITCH
- - - - STANDARD DITCH
- ⊠ - RIPRAP
- ◇ - TEMP. DITCH CHECK

SEC. 15, T27N, R7E, 3RD P.M.

ESTATE OF STUART W. MILLER

MILLER HAMS, INC.

MILLER HAMS, INC.

ESTATE OF STUART W. MILLER

REPORTED 6" PVC WASTE LINE - TO BE ADJUSTED BY OTHERS. WASTE LINE IS OUTLET FROM HOG FARM.

STA. 1044+02  
EXIST. 3'X2' BOX - 52'  
USFL - 668.02 LT. 26'  
DSFL - 667.77 RT. 26'

STA. 1044+02  
REMOVE EXISTING END SECTIONS EXTENDING PCBC W/ PCBC 3'X2' - 6' LT. & 6' RT. W/ BOX CULVERT END SECTIONS - 2 EA.  
USFL - 668.04  
DSFL - 667.76  
(BOX CULVERT TO BE CLEANED)

STA. 1046+50, 33' LT.  
PIPE CULVERT, CLASS D, TYPE 1 - 15"  
END SECTIONS - 15"

STA. 1050+05, 25.9' LT.  
EXIST. 15" CMP - 26'  
USFL - 672.74  
DSFL - 672.56  
(TO BE REMOVED)

STA. 1050+05, 33' LT.  
PIPE CULVERT, CLASS D, TYPE 1 - 15"  
END SECTIONS - 15"

STA. 1043+39, 28' LT.  
EXIST. 18" CMP - 50'  
USFL -  
DSFL -  
(TO BE REMOVED)

STA. 1044+02±  
EXIST. - UNKNOWN  
USFL - UNKNOWN  
DSFL - UNKNOWN

REPORTED FIELD TILE (SEE GENERAL NOTES - FIELD TILE WORK)

STA. 1047+37, 24.4' RT.  
EXIST. 15" CMP - 26'  
USFL - 671.03  
DSFL - 670.65  
(TO BE REMOVED)

STA. 1047+37, 33' RT.  
PIPE CULVERT, CLASS D, TYPE 1 - 15"  
END SECTIONS - 15"

STA. 1050+06, 25.7' RT.  
EXIST. 15" CMP - 32'  
USFL - 673.38  
DSFL - 673.28  
(TO BE REMOVED)


STA. 1050+30, 33' RT.  
PIPE CULVERT, CLASS D, TYPE 1 - 15"  
END SECTIONS - 15"

MARY A. HALEY, TRUSTEE

JANET K. MILLER, TRUSTEE

SEC. 16, T27N, R7E, 3RD P.M.

BM#43 CHISLED SQUARE ON EAST HEADWALL OF BOX CULVERT  
26.1' LT. STA. 1044+02 ELEV. 670.35



PLAN

DATE	
BY	
REVIEWED	
PLOTTED	
NOTE BOOK	
NO. _____	

PROFILE

DATE	
BY	
REVIEWED	
PLOTTED	
NOTE BOOK	
NO. _____	

