

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	•	LIVINGSTON	354	61
STA. 1160+00		TO STA. 1175+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
•(123,123)RS-3,(124)RS-5,(123)BR-3				

LEGEND

- X - TREE REMOVAL
- [Hatched Box] - PAVEMENT REMOVAL & CLASS D PATCH
- [Wavy Line] - SPECIAL DITCH
- [Wavy Line] - STANDARD DITCH
- [Cross-hatched Box] - RIPRAP
- [Diamond] - TEMP. DITCH CHECK

SEC. 27, T27N, R7E, 3RD P.M.

ELEANOR DENKER, LIFE ESTATE


JEFFREY GUTWEIN &
WENDY GUTWEIN, TRUSTEES
SEC. 28, T27N, R7E, 3RD P.M.

STA. 1171+32.5
EXIST. 45"X28" ELLIP. CONC. PIPE - 51'
USFL - 720.20 LT. 27'
DSFL - 719.91 RT. 24'
STA. 1171+32.5
EXISTING CONCRETE PIPE, ERS 36"
REMOVE EXISTING END SECTIONS
EXTEND WITH PIPE CULVERTS,
CLASS A, TYPE 1 ERS 36"
4' LT. & 8' RT.
W/PRC FLARED END SECTIONS
ERS 36" - 2 EA.
USFL - 720.21
DSFL - 719.88
(CULVERT TO BE CLEANED)

STA. 1173+66, 27.5' RT.
EXIST. 18" CMP - 16'
USFL - 721.13
DSFL - 721.05
(TO BE REMOVED)

STA. 1173+67, 36' RT.
PIPE CULVERT,
CLASS D, TYPE 1 - 24"
END SECTIONS - 24"

BM#22 CHISEL SQUARE IN PAVEMENT
NEAR PAVEMENT STAMP 1167
12.3' RT. STA. 1167+14 ELEV. 726.62



PLAN

DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	

PROFILE

DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	

