

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	ROADWAY
			90% FED 10% STATE I000-2A
50104400	CONCRETE HEADWALL REMOVAL	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	448
50800105	REINFORCEMENT BARS	POUND	32
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	24
54213450	END SECTIONS 15"	EACH	16
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1
54248510	CONCRETE COLLAR	CU YD	1.5
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	318
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	13
66700095	PERMANENT SURVEY MARKERS	EACH	8
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3420.7
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	234
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16226
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1424
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	740
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	27
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	380
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	234
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16226
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1424
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	740
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	186
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	41
X4020500	AGGREGATE SURFACE COURSE, TYPE B 6"	SQ YD	403.1
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	69
Z0032900	LAND SECTION MARKERS	EACH	2
Z0041500	PLUG EXISTING CULVERTS	EACH	2

* SPECIALTY ITEMS

FILE NAME = c:\projects\006\plans\shs.dgn	USER NAME = fergusonse	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 567	SECTION 34 N & N-1	COUNTY DEKALB	TOTAL SHEETS 62	SHEET NO. 4	
PLOT SCALE = 20.0000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE = Dec 17, 2007 - 08:12:06 AM	DATE -	REVISED -	CONTRACT NO. 66632								