SEEDING & EROSION CONTROL SCHEDULE

LOCATION	SIDE	SEEDING CL 2A	SODDING	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	INLET AND PIPE PROTECTION	TEMPORARY DITCH CHECK
LOCATION		ACRE		ACRE	POUNDS	POUNDS	POUNDS	POUNDS	FEET	SQ YD	SQ YD	EACH
LIVINGSTON												
STA. 309+95 TO STA. 313+30	LT	0.09		0.09	8.4	7.7	7.7	7.7	76		1	1
STA. 309+95 TO STA. 321+10	RT	0.26	953.00	0.26	35.5	23.0	23.0	23.0	1038		1	2
STA. 313+30 TO STA. 321+10	LT	0.18		0.18	18.9	16.4	16.4	16.4			1	1
STA. 321+10 TO STA. 324+90	LT	0.16		0.16	15.7	14.0	14.0	14.0			1	1
STA. 321+10 TO STA. 332+35	RT	0.48		0.48	58.1	42.8	42.8	42.8	327	16	4	2
STA. 324+90 TO STA. 328+10	LT	0.12		0.12	12.0	11.0	11.0	11.0	293		3	
STA. 328+10 TO STA. 329+40	LT	0.03		0.03	2.8	2.7	2.7	2.7			2	
STA. 329+40 TO STA. 331+55	LT	0.03		0.03	2.2	2.4	2.4	2.4			1	
STA. 331+55 TO STA. 334+10	LT	0.06		0.06	5.9	5.6	5.6	5.6			1	
STA. 332+35 TO STA. 335+85	RT	0.17		0.17	19.3	15.0	15.0	15.0			2	
STA. 334+10 TO STA. 340+31	LT	0.32		0.32	32.5	29.0	29.0	29.0			1	1
STA. 335+85 TO STA 340+31	RT	0.19		0.19	21.8	17.3	17.3	17.3			2	1
LINE TOTAL		2.1	953.0	2.1	233.2	187.1	187.1	187.1	1734	16	20	9

1. NOTE: QUANTITY FOR TEMPORARY SEEDING AVALIABLE FOR 6 APPLICATIONS

EARTHWORK SCHEDULE

LOCATION BUREAU COUNTY	EARTH EXCAVATION	EARTH EX. ADJUSTED FOR SHRINKAGE (0.75)	EMBANKMENT	WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD
STA 309+95 TO STA 315+53	539.94	404.96	377.45	27.51
STA 315+53 TO STA 321+21.96	573.82	430.37	571.15	-140.79
STA 321+21.96 TO STA 326+98	1105.7	829.28	622.32	206.96
STA 326+98 TO STA 334+33.79	903.24	677.43	360.09	317.34
STA 334+33.79 TO STA 340+31	990.94	743.21	247.77	495.44
DONNYBROOK LANE		0.00		0.00
VIRGINIA DRIVE		0.00		0.00
TOTAL	4113.64 *	3085.23	2178.78	906.45

* Pay Items

RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION		ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER	REFLECTOR REMOVAL
		LIN FT	LIN FT	LIN FT	LIN FT
	ft	EACH	EACH	EACH	EACH
STA. 309+95 TO STA 310+33	38			1	1
STA. 310+33 TO STA 318+18	785		40		10
STA. 318+18 TO STA 320+83	265	7		14	3
STA. 321+68 TO STA 324+33	265	10	8	6	3
STA. 322+88 TO STA 331+29	841		42		11
STA. 331+29 TO STA 333+94	265	7		14	3
STA. 334+82 TO STA 337+47	265	7			3
STA. 334+55 TO STA 340+03.5	548.5		30		7
PROJECT TOTAL		30	120	36	41

MAINLINE SCHEDULE

LOCATION IL 116	LENGTH	WIDTH	AREA	HOT-MIX ASPHALT SURFACE COURSE MIX D, N70	LEVELING BINDER (MACHINE) (METHOD) N70	STRIP REFLECTIVE CRACK CONTROL SYSTEM	HMA BASE COURSE WIDENING	HOT-MIX ASPHALT SHOULDERS	AGG. SHLDR TY B	SUB-BASE GRANULAR MATERIAL TYPE A	SUB-BASE GRANULAR MATERIAL TYPE A	SUB-BASE GRANULAR MATERIAL TYPE A	BIT. PRIME COAT	MIX FOR CRACKS JOINTS AND FLANGEWAYS	AGG PRIME COAT	LEVEL BINDER HAND METHOD	TEMP RAMP
				1 1/2"	1"		8"	8"	6"	12"	18"	24"					
	FT	FT	SQ YD	TONS	TONS	FOOT	SQ YD	SQ YD	TONS	SQ YD	SQ YD	SQ YD	GALLONS	TONS	TONS	TONS	SQ YD
LIVINGSTON COUNTY																	
309+95 TO 315+53	558.0	31.0	1922	161.4	107.6	1116.0	802.2	248.0	169.5	342.3	782.1		173.6	0.6	4.34	1.1	13.3
315+53 TO 320+46.5	493.5	38.0	2083.7	175.0	116.7	987.0	767.5	219.3	149.9	1041.7			184.3	0.6	4.61	1.1	
DONNYBROOK LANE	VAR	VAR.	781.4	65.6	43.8		382.2			395.7			62.5	0.2	1.56	0.4	13.3
321+68 TO 324+33	265.0	50.0	1472.2	123.7	82.4	530.0	796.6	235.6	40.2	1061.6			136.6	0.4	3.41	0.8	
324+33 TO 326+98	265.0	44.0	1295.6	108.8	72.6	530.0	633.3	235.6	40.2	697.9		200.4	122.5	0.4	3.06	0.7	
326+98 TO 333+44	646.0	38.0	2727.6	229.1	152.7	1292.0	1390.4	287.1	196.2	1749.2			241.2	0.8	6.03	1.5	
VIRGINIA DRIVE	VAR	VAR.	896.4	75.3	50.2		410.4	144.4		570.1			83.3	0.3	2.08	0.5	13.3
334+82 TO 337+47	265.0	47.0	1383.9	116.2	77.5	530.0	715.1	235.6	40.2	980.1			129.6	0.4	3.24	0.8	
337+47 TO 340+31	284.0	34.0	1072.9	90.1	60.1	568.0	341.0	252.4	43.1	625.0			106.0	0.3	2.65	0.6	13.3
LINE TOTAL			10640.8	1145.2	763.6	5553.0	6238.7	1858.0	679.4	7463.6	782.1	200.4	1239.5	4.1	31.0	7.5	53.3