DRAINAGE SCHEDULE

STATION	SIDE	PIPE CULVERT REMOVAL	CONCRETE HEADWALL REMOVAL	PLUG EXISTING CULVERT	PIPE CULV. TY. 1 RCCP 30'	PRECAST REINFORCED CONCRETE FLARED END SECT 30"	GRATING FOR CONCRETE FLARED END SECT 30"	CONC. COLLAR	REINFOR. BARS	PIPE CULV. CLASS D TYPE 1 15"	END SECTIONS 15"
		FOOT	EACH	EACH	FOOT	EACH	EACH	CU YD	POUND	FOOT	EACH
STA 313+41	LT	50								44	2
STA 320+42	RT	48									
STA 321+22	LT	51		2							
STA 321+22	RT									25	2
STA 325+02	LT	44								44	2
STA 327+24.16	RT	20	1		24	1	1	1.5	32		
STA 328+21	LT	45								44	2
STA 329+50	LT	46								40	2
STA 331+62	LT	45								44	2
STA 332+50	RT	56								45	2
STA 335+93	RT	43								32	2
TOTAL		448	1	2	24	1	1	1.5	32	318	16

ENTRANCE SCHEDULE

STATION	TYPE	WIDTH FEET	SIDE	AREA SQ FT	AGGREGATE FOR TEMPORARY ACCESS TON	AGGREGATE SURFACE COURSE TY. B 6" SQ YD	AGGREGATE BASE COURSE TY. A, 6" SQ YD	FURNISHED EMBANKMENT CU YD	INCIDENTAL BITUMINOUS SURFACE TON
STA 313+41	F.E.	24	LT	1037	6	115.2		35	
STA 320+42	P.E.	10	RT	REMOVE EXISTING ENTRANCE					
STA 321+22	P.E. + MBTO	12-15	RT	2557.2	15		284.1	50	3.3
STA 325+02	F.E.	24	LT	888.8	6	98.8		40	
STA 328+21	F.E.	24	LT	854	6	94.9		14	
STA 329+50	P.E. + MBTO	20	LT	822.7	10		91.4	14	1.1
STA 331+62	F.E.	24	LT	847.7	6	94.2		14	
STA 332+50	C.E.	25	RT	1008.5	10		112.1	20	1.3
STA 335+93	P.E. + MBTO	12	RT	651.6	10		72.4	30	0.8
TOTAL					69	403.1	560	217	6.5

TREE REMOVAL SCHEDULE

STATION	OFFSET FOOT	OVER 15 UNIT DIA.
320+54	155' RT	20
325+00	42' RT	20
326+13	43' RT	20
TOTAL		60