

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
41	12 I	KANKAKEE	21	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

ITEM NO.	ITEM	UNIT	80% FED 20% STATE		
			TOTAL QUANTITY	ROADWAY 1000	CULVERT Y007
20200100	EARTH EXCAVATION	CU YD	203	203	--
20400800	FURNISHED EXCAVATION	CU YD	74	74	--
20700220	POROUS GRANULAR EMBANKMENT	CU YD	169	169	--
25000210	SEEDING, CLASS 2A	ACRE	0.7	0.7	--
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63	63	--
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63	63	--
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63	63	--
25100115	MULCH, METHOD 2	ACRE	0.7	0.7	--
25100630	EROSION CONTROL BLANKET	SQ YD	120	120	--
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	286	286	--
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	--
28000500	INLET AND PIPE PROTECTION	EACH	3	3	--
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	227	227	--
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	207	207	--
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	40	40	--
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	--
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	160	160	--
40600300	AGGREGATE (PRIME COAT)	TON	3	3	--
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	0.4	0.4	--
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	63	63	--
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	440	440	--
40600990	TEMPORARY RAMP	SQ YD	27	27	--
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	168	168	--
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	7	7	--
44000100	PAVEMENT REMOVAL	SQ YD	165	165	--
44004250	PAVED SHOULDER REMOVAL	SQ YD	333	333	--
48101200	AGGREGATE SHOULDERS, TYPE B	TON	135	135	--
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	--	1
50105200	REMOVE EXISTING CULVERTS	EACH	2	2	--
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	59	--	59
51500100	NAME PLATES	EACH	1	--	1
X0325919	PRECAST CONCRETE BOX CULVERT END SECTIONS 7'X3' (SPECIAL)	EACH	4	--	4
X0325918	PRECAST CONCRETE BOX CULVERT 7' X 3' (SPECIAL)	FOOT	168	--	168

ITEM NO.	ITEM	UNIT	80% FED 20% STATE		
			TOTAL QUANTITY	ROADWAY 1000	CULVERT Y007
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	48	48	--
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	45	45	--
542D5497	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	34	34	--
54213450	END SECTIONS 15"	EACH	3	3	--
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	--
54215970	REINFORCED CONCRETE PIPE ELBOW 15"	EACH	1	1	--
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	--
67100100	MOBILIZATION	L SUM	1	1	--
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	--
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	--
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	--
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	--
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	7	--
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	--
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	120	120	--
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20	20	--
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5	362.5	--
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5	--
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1200	1200	--
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	150	150	--
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	--
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	--
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	--
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	--
XX003404	TEMPORARY PAVEMENT, 8"	SQ YD	760	760	--
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	115	--	115
X0325907	GRATING FOR PRECAST CONCRETE BOX CULVERT END SECTION 7' X 3'	EACH	4	--	4

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 41 (IL 17)
 SECTION 12 I
 KANKAKEE COUNTY

SCALE: VERT.
 HORIZ.
 DATE: 10/07

DRAWN BY: LAG
 CHECKED BY: JKC