

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
41	12 I	KANKAKEE	21	4
STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		

EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
	(A)	(B)	[(A)0.75]-(B)	
STAGE I	64	79	-31	-
STAGE II	55	52	-11	-
STAGE III	53	57	-17	-
STAGE IV	31	38	-15	-
TOTAL	203	226	74	
	PAY ITEM		PAY ITEM	

PAVEMENT SCHEDULE										
LOCATION (STA TO STA)	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	HOT-MIX ASPHALT BASE COURSE, 10"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N70	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	AGGREGATE SHOULDER, TYPE B
STA 1187+49 TO STA 1188+11, LT. & RT.	227	207	--	--	--	--	--	165	--	--
STA 1185+00 TO STA 1191+00, LT. & RT.	--	--	160	3	0.4	63	168	--	--	135
STA 1185+62.0 TO STA 1190+00.5, LT.	--	--	--	--	--	--	--	--	122	--
STA 1185+49.5 TO STA 1190+13.0, RT.	--	--	--	--	--	--	--	--	211	--
TOTAL	227	207	160	3	0.4	63	168	165	333	135

EROSION CONTROL BLANKET	
LOCATION	SQ YD
STA 1184+94, RT.	10
STA 1186+90.18, LT.	10
STA 1187+23.24, LT.	10
STA 1187+46.06, LT.	40
STA 1187+55.55, RT.	10
STA 1188+13.94, RT.	40
TOTAL	120

HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	
LOCATION	SQ YD
STA 1185+00 TO STA 1185+60, LT. & RT.	240
STA 1190+40 TO STA 1191+00, LT. & RT.	200
TOTAL	440

TEMPORARY DITCH CHECK	
LOCATION	EACH
STA 1188+40, LT. & RT.	2
TOTAL	2

TEMPORARY RAMP	
LOCATION	SQ YD
STA 1185+00, LT. & RT.	13.5
STA 1191+00, LT. & RT.	13.5
TOTAL	27.0

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA 1185+00 TO STA 1191+00	8
TOTAL	8

ENTRANCE SCHEDULE		
LOCATION (STA TO STA)	AGGREGATE SURFACE COURSE, TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING
	TON	TON
STA 1185+27.0, RT - PRIVATE ENTRANCE	--	4
STA 1187+08.3, LT - FIELD ENTRANCE, 17' WIDE	26	--
STA 1187+77.0, RT - PRIVATE ENTRANCE, 18' WIDE	14	3
TOTAL	40	7

INLET AND PIPE PROTECTION	
LOCATION	EACH
STA 1184+94, RT.	1
STA 1186+90.18, LT.	1
STA 1187+55.55, RT.	1
TOTAL	3

THERMOPLASTIC PAVEMENT - LINE 4"	
LOCATION	FOOT
STA 1185+00 TO STA 1191+00, LT. & RT.	1200
TOTAL	1200

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA 1185+00 TO STA 1191+00	8
TOTAL	8

THERMOPLASTIC PAVEMENT - LINE 6"	
LOCATION	FOOT
STA 1185+00 TO STA 1191+00	150
TOTAL	150

TEMPORARY PAVEMENT, 8"	
LOCATION	SQ YD
STA 1185+62.0 TO STA 1190+00.5, LT.	397
STA 1185+49.5 TO STA 1190+13.5, RT.	363
TOTAL	760

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 41 (IL 17)
 SECTION 12 I
 KANKAKEE COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE: 10/07

DRAWN BY: LAG
 CHECKED BY: JKC