

## SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: **Y007**

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	50.2
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	50
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10
50102400	CONCRETE REMOVAL	CU YD	18
50200100	STRUCTURE EXCAVATION	CU YD	50.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3190
54003000	CONCRETE BOX CULVERTS	CU YD	18
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	87
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	24
63200310	GUARDRAIL REMOVAL	FOOT	124
67100100	MOBILIZATION	L SUM	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	61
X0323115	REFLECTOR MARKERS, TYPE A	EACH	2
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	704
X0321781	MECHANICAL SPLICE	EACH	48
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	2

\*SPECIALTY ITEM