

| | | | | |
|---------------------|-----------|----------|------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 318 | 72-16-LRS | PEORIA | 89 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

SUMMARY OF QUANTITIES

| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | ACNHF | | ACHSIP | | Y031-1F 90% FED 5% STATE 2.5% PEORIA CO. 2.5% MEDINA TWP | Y080 | 07A |
|------------|---|--------|----------------|---------------|---------------|------------------|------------------|--|------|-----|
| | | | | I000 80/20 | I000 90/10 | Y031-1F 80/20 | Y031-1F 80/20 | | | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 0.8 | 0.2 | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 0.8 | 0.2 | | | | | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 25 | 20 | 5 | | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 24 | 19.2 | 4.8 | | | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 5,662 | 5,662 | | | | | | |
| 70300610 | TEMP PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS | SQ FT | 473 | 473 | | | | | | |
| 70300625 | TEMPORARY PAINT PAVEMENT MARKING LINE 4" | FOOT | 22,830 | 22,830 | | | | | | |
| 70300635 | TEMPORARY PAINT PAVEMENT MARKING LINE 6" | FOOT | 1,500 | 1,500 | | | | | | |
| 70300640 | TEMPORARY PAINT PAVEMENT MARKING LINE 8" | FOOT | 6,353 | 6,353 | | | | | | |
| 70300645 | TEMPORARY PAINT PAVEMENT MARKING LINE 12" | FOOT | 2,063 | 2,063 | | | | | | |
| 70300660 | TEMPORARY PAINT PAVEMENT MARKING LINE 24" | FOOT | 249 | 249 | | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1,142 | 1,142 | | | | | | |
| 78003100 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS</i> | SQ FT | 473 | 473 | | | | | | |
| 78003110 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"</i> | FOOT | 22,830 | 22,830 | | | | | | |
| 78003130 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"</i> | FOOT | 1,500 | 1,500 | | | | | | |
| 78003140 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"</i> | FOOT | 6,353 | 6,353 | | | | | | |
| 78003150 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"</i> | FOOT | 2,063 | 2,063 | | | | | | |
| 78003180 | <i>PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"</i> | FOOT | 249 | 249 | | | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 700 | 700 | | | | | | |
| 78300200 | RAISE REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 800 | 800 | | | | | | |
| 80500200 | SERVICE INSTALLATION, TYPE B | EACH | 1 | | | | 1 | | | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 2,351 | | | 636 | 1,715 | | | |
| 81012800 | CONDUIT IN TRENCH, 3" DIA., PVC | FOOT | 150 | | | 48 | 102 | | | |

*SPECIALTY ITEM

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE
HORIZ.

DRAWN BY
CHECKED BY