

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	72-6-URS	PEORIA	89	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ACNHF		ACHSIP		Y080	07A
				I000 80/20	I000 90/10	Y031-1F 80/20	Y031-1F 90% FED 5% STATE 2.5% PEORIA CO. 2.5% MEDINA TWP.		
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	120			78	42		
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	172			77	95		
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	297			84	213		
81021360	CONDUIT PUSHED, 3 1/2" DIA., PVC	FOOT	207			105	102		
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	14			6	8		
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2			1	1		
81702130	ELECTRIC CABLE IN CONDUIT, 600 V(XLP-TY USE)1/C NO. 6	FOOT	1,338				1,338		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,614			760	1,854		
85700205	FULL-ACTUATED CONTROLLER <sup>AND</sup> TYPE IV CABINET, SPECIAL	EACH	1				1		
85700300	FULL-ACTUATED CONTROLLER <sup>AND</sup> TYPE V CABINET	EACH	1			1			
86000105	MASTER CONTROLLER (SPECIAL)	EACH	1				1		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,800.5			1993.5	807		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,894.5			355.5	1,539		
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	2,081.5			265.5	1,816		
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	3			1	2		
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	2				2		
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1			1			
87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	2				2		
87702700	STEEL <sup>MAST ARM</sup> ASSEMBLY AND POLE WITH DUAL <sup>ARMS,</sup> MAST <sup>AND</sup> 44 FT. 50 FT.	EACH	1			1			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9			3	6		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7			3.5	3.5		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20				20		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	76			34	42		
87900200	DRILL EXISTING HANDHOLE	EACH	1			1			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY