

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	72-(6-1)RS	PEORIA	89	17
IL 6				
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SODDING, SALT TOLERANT	
LOCATION	SQ YD
IL 29 STA. 32+97.5 TO STA. 44+93.22	2,657
<b>TOTAL</b>	<b>2,657</b>

SUPPLEMENTAL WATERING	
LOCATION	UNIT
IL 29 STA. 32+97.5 TO STA. 44+93.22	50
<b>TOTAL</b>	<b>50</b>

INCIDENTAL HOT-MIX ASPHALT SURFACING	
LOCATION	TON
IL 6	
STA. 0+32.00 TO STA. 13+60.80	200
<b>TOTAL</b>	<b>200</b>

TEMPORARY DITCH CHECKS	
LOCATION	EACH
RT. STA. 7+70 (IL6)	1
RT. STA. 329+50 (STATE ST.)	1
RT. STA. 330+30 (STATE ST.)	1
LT. STA. 334+00 (OLD GALENA RD.)	1
LT. STA. 336+50 (OLD GALENA RD.)	1
<b>TOTAL</b>	<b>5</b>

TEMPORARY RAMP	
LOCATION	SQ YD
<b>IL 29</b>	
LT. STA. 32+97.28 TO LT. STA. 33+07.28	26.67
LT. STA. 54+85.69 TO LT. STA. 54+95.69	33.05
RT. STA. 32+97.28 TO RT. STA. 33+07.28	24.45
RT. STA. 54+85.69 TO RT. STA. 54+95.69	34.67
<b>IL 6</b>	
LT. STA. 13+50.80 TO LT. STA. 13+60.80	31.14
LT. STA. 26+17.36 TO LT. STA. 26+27.36	19.47
RT. STA. 13+50.80 TO RT. STA. 13+60.80	39.27
RT. STA. 26+17.36 TO RT. STA. 26+27.36	19.34
<b>RAMP B</b>	
⊕ STA. 20+00.00 TO ⊕ STA. 20+10.00	17.78
<b>OLD GALENA ROAD</b>	
STA. 323+25.19 TO STA. 323+30.19	14.48
<b>STATE STREET</b>	
STA. 331+86.59 TO STA. 331+91.59	11.11
<b>TOTAL</b>	<b>271</b>

PERIMETER EROSION BARRIER	
LOCATION	FOOT
(IL 29) RT. STA. 44+75 TO (OLD GALENA) RT. STA. 334+30	822
(IL 29) RT. STA. 50+15 TO (STATE ST) RT. STA. 328+25	843
(OLD GALENA) LT. STA. 337+00 TO (IL 6) RT. STA. 8+50	615
(STATE ST.) LT. STA. 329+85 TO (IL 6) LT. STA. 8+50	321
<b>TOTAL</b>	<b>2,601</b>

EROSION CONTROL BLANKET	
LOCATION	SQ YD
RT. STA. 43+99 (IL 29) TO RT. STA. 2+95 (IL 6)	444.4
LT. STA. 1+50 (IL6) TO RT. STA. 329+75 (STATE ST.)	555.6
LT. STA. 329+75 (STATE ST.) TO LT. STA. 9+16 (IL 6)	500
RT. STA. 337+32.31 (GALENA) TO RT. STA. 5+00 (IL 6)	638.9
LT. STA. 333+00 TO LT. STA. 336+50 (GALENA)	520
<b>TOTAL</b>	<b>2,659</b>

EARTH WORK					
LOCATION	EARTH EXCAV.	ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTH BALANCE WASTE(+) SHORTAGE(-)	TOPSOIL FURN. 4"
	CU YD	CU YD	CU YD	CU YD	SQ YD
OLD GALENA LT. STA. 332+00 TO 337+00	75.0	56.0	175.0	-119.0	520
STATE ST. RT. STA. 328+50 TO 330+50	3.0	2.25	15.0	-13.0	122
IL 29 & IL 6 RT. STA. 45+00 TO 2+50	523.0	392.0	0.0	+392.0	780
<b>TOTAL</b>	<b>601.0</b>	<b>450.25</b>	<b>190.0</b>	<b>+260.25</b>	<b>1,422</b>

PATCHING SHEDULE			
LOCATION	CLASS B PATCHES, TYPE II, 11 INCH	CLASS D PATCHES, TYPE II, 14 INCH	CLASS D PATCHES, TYPE IV, 14 INCH
	SQ. YD.	SQ. YD.	SQ. YD.
<b>IL 29</b>			
⊕ STA. 32+98.00 TO ⊕ STA. 54+95.00		50	175
<b>IL 6</b>			
⊕ STA. 13+60.80 TO STA.18+00.00 & RAMP B ⊕ STA. 20+00.00 TO ⊕ STA. 28+66.41	100		
<b>TOTAL</b>	<b>100</b>	<b>50</b>	<b>175</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION	
<b>SCHEDULE OF QUANTITIES</b>	
SCALE: VERT. _____	DRAWN BY _____
DATE _____	CHECKED BY _____

PLOT DATE: 12/17/2007  
 PLOT SCALE: 1/8"=1'-0"  
 USER NAME: jbruce