

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	72-16-11RS	PEORIA	89	20
IL 6				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	
LOCATION	SQ YD
<b>IL 29</b>	
RT. STA. 32+97.28 TO STA. 33+27.28	80
LT. STA. 32+97.28 TO STA. 33+27.28	80
RT. STA. 54+65.69 TO STA. 54+95.69	103
LT. STA. 54+65.69 TO STA. 54+95.69	105
<b>OLD GALENA ROAD</b>	
STA. 337+32.35 TO STA. 337+02.35	86.91
<b>STATE STREET</b>	
STA. 328+62.5 TO STA. 328+92.5	66.67
<b>IL 6</b>	
RT. STA. 13+60.8 TO STA. 13+90.8	146.6
LT. STA. 13+60.8 TO STA. 13+90.8	106.7
RT. STA. 26+00 TO STA. 26+30	80
LT. STA. 26+00 TO STA. 26+30	80
<b>TOTAL</b>	<b>935</b>

HOT-MIX ASPHALT SURFACE REMOVAL 2"	
LOCATION	SQ YD
<b>IL 29</b>	
RT. STA. 33+27.28 TO STA. 46+19.72	7,614
LT. STA. 33+27.28 TO STA. 46+19.72	7,163
<b>OLD GALENA ROAD/SHOULDERS</b>	
STA. 331+75 TO STA. 337+02.35	2,707
<b>STATE STREET/SHOULDERS</b>	
STA. 328+92.5 TO STA. 331+20	1,203
<b>SHOULDERS IL 29</b>	
LT. STA. 32+97.28 TO STA. 54+95.69	1,954
RT. STA. 32+97.28 TO STA. 45+62	1,124.2
RT. STA. 48+73 TO STA. 54+95.69	553.5
<b>SHOULDERS IL 6</b>	
RT. STA. 13+60.8 TO STA. 26+30	1,128.2
LT. STA. 13+60.8 TO STA. 26+30	1,128.2
<b>TOTAL</b>	<b>24,575</b>

ISLAND REMOVAL	
LOCATION	SQ FT
OLD GALENA RD. RT. STA. 331+93	576.5
STATE ST. RT. STA. 331+00	417.7
IL 6 RT. STA. 1+92	4,382
IL 6 LT. STA. 1+33	4,885
IL 29 LT. STA. 46+41	1,306
<b>TOTAL</b>	<b>11,568</b>

CONCRETE MEDIAN REMOVAL	
LOCATION	SQ FT
<b>IL 6</b>	
STA. 6+07 TO STA. 9+67	3,045
STA. 0+45 TO STA. 5+28	7,136
<b>IL 29</b>	
STA. 32+97.5 TO STA. 46+33	796
<b>TOTAL</b>	<b>10,977</b>

BITUMINOUS CONCRETE SHOULDER REMOVAL	
LOCATION	SQ YD
<b>IL 6</b>	
LT. STA. 0+56.00 TO LT. STA. 4+51.88	319.68
LT. STA. 6+13.68 TO LT. STA. 13+60.80	657.33
RT. STA. 0+44.00 TO RT. STA. 5+08.51	379.04
RT. STA. 6+97.52 TO RT. STA. 13+60.80	579.76
<b>OLD GALENA ROAD</b>	
LT. STA. 332+70.87 TO LT. STA. 337+32.35	269.69
<b>STATE STREET</b>	
RT. STA. 329+53.98 TO RT. STA. 331+91.59	92.73
<b>TOTAL</b>	<b>2298</b>

COMBINATION CONCRETE CURB AND GUTTER REMOVAL	
LOCATION	FOOT
<b>IL 29 MEDIANS</b>	
STA. 32+97.28 TO STA. 44+93.22	1,295.2
<b>IL 6 MEDIANS</b>	
STA. 0+46.36 TO STA. 4+68.66	847.8
STA. 8+16.99 TO STA. 13+60.8	1,087
<b>TOTAL</b>	<b>3,230</b>

PAVEMENT REMOVAL	
LOCATION	SQ YD
<b>IL 29</b>	
LT. STA. 32+97.28 TO STA. 46+51.73	1,304
<b>IL 6</b>	
RT. STA. 0+32 TO STA. 13+60.8	4,248.6
LT. STA. 0+32 TO STA. 13+60.8	4,169.4
<b>TOTAL</b>	<b>9,722</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLOT DATE = 12/17/2007  
 FILE NAME = S:\GIS\BENTLEY\STIP\PLANS\68110\68110-Cover-sheet & SOQ.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = brucebbs