

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	446-1RS-7	PEORIA	62	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Environmental Survey Request)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form
- * Color photographs depicting the use area

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

PLAN NOTES

Construction activities may need to be coordinated with Contract #68480 (deck beam replacement on S.N. 072-0134 carrying US 24 over Kickapoo Creek).

There shall be no lane closures on US 24 or at the Adams Street/Washington Street intersection before 8:00 AM or after 3:00 PM on weekdays. Weekend work will have no time restrictions.

Striping operations may be performed between 8:00 AM and 3:00 PM weekdays, after 6:00 PM weekdays, or any time on the weekend, at the discretion of the Resident Engineer.

STATUS OF UTILITIES TO BE ADJUSTED

Company	Offset	Location	Type of Utility	Type of Conflict	Disposition
Illinois American Water	7' Rt. To 22' Lt.	Sta. 76+92.71 - 186+28.99	6" Water Main	Under Roadway	Relocate

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		COMMITMENTS, GENERAL NOTES, & PLAN NOTES SCALE: VERT. _____ DATE _____ DRAWN BY _____ CHECKED BY _____