

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	08PPP	DEWITT	11	5

SCHEDULE OF QUANTITIES

**PERMANENT SURVEY MARKERS
TO BE PRESERVED
(COST INCIDENTAL TO CONTRACT)**

CL. STA.	EACH
171+03.831	1
192+84.80	1
TOTAL =	2 EACH

**PAINT PAVEMENT MARKINGS LINE 24"
(78001180)**

RAILROAD CROSSING:

LT. 124+50 ~ (1' - 11') RT. = 36 FT
RT. 124+85 ~ (1' - 11') RT. = 36 FT

IL 105/1L 54 INTERSECTION:

LT. 69+50 = 17 FT
RT. 68+75 = 17 FT

TOTAL= 106 FT

PAVEMENT MARKINGS

STATION	TO STATION	4"	4"	4"	SHORT TERM	WORK ZONE
		SKIP DASH YELLOW (FOOT) (78001110)	NO PASSING YELLOW (FOOT) (78001110)	EDGE LINE WHITE (FOOT) (78001110)	PAVEMENT MARKINGS (FOOT) (70300100)	PAVEMENT MARKING REMOVAL (SQ.FT.) (70301000)
0+00	55+50	1,398	0	11,100	1,110	185
55+50	62+54	0	0	0	0	0
62+54	68+75	165	0	1,242	124	21
68+75	69+50	29	0	150	0	0
69+50	77+50	210	0	1,600	160	27
77+50	82+50	0	1,000	1,000	100	17
82+50	97+50	385	0	3,000	300	50
97+50	107+50	260	2,000	2,000	200	33
107+50	124+50	435	0	3,400	340	57
124+50	124+85	0	70	70	7	1
124+85	264+37	3,498	0	27,904	2,790	465
SUB-TOTAL		6,380	3,070	51,466	5,132	855
TOTAL 4"		60,916				

**THERMOPLASTIC PAVEMENT MARKINGS LETTERS & SYMBOLS
(78000100)**

STA. RT. '122+29 ~ RT. 122+59 (1.5 ~ 9.5' RT.) = X = 54.0 SQ FT
STA. RT. '122+40 ~ RT. 122+50 = R = 3.6 SQ FT
STA. RT. '122+40 ~ RT. 122+50 = R = 3.6 SQ FT
STA. LT. '122+97 ~ LT. 122+70 (1.5 ~ 9.5' LT.) = X = 54.0 SQ FT
STA. LT. '122+72 ~ 122+87 = R = 3.6 SQ FT
STA. LT. '122+72 ~ 122+87 = R = 3.6 SQ FT
TOTAL= 123.0 SQ.FT.

**RAISED REFLECTIVE PAVEMENT MARKER
(78100100)**

STATION TO STATION	EACH
0+00 264+36.5	333

**RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
(78300200)**

STATION TO STATION	EACH
0+00 264+36.5	333

PLOT DATE: 18/17/2007
 FILE NAME: c:\projects\70673\1517\151724quant.dgn
 PLOT SCALE: 42.3529 / IN.
 USER NAME: callierb

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.S. 1517 (U.S. 150)
SECTION 08PPP
CHAMPAIGN COUNTY

SCALE: N/A
DATE: 08/28/07

DRAWN BY: RC
CHECKED BY: MAL