

SCHEDULE OF QUANTITIES

CLASS B PATCHING

BEGINNING STATION	ENDING STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA			DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
						TYPE III 15.0" (sq. yd)	TYPE IV • (sq. yd)	TYPE IV 10.0" (sq. yd)				
1105+65.00	1106+33.18	EASTBOUND	DL	68.18	12.1	0.0	91.7	0.0	34	160.6	35	91.7
1105+65.00	1106+33.18	EASTBOUND	PL	68.18	12.1	0.0	91.7	0.0	34	92.4	0	91.7
1106+33.18	1108+27.18	EASTBOUND	DL	194	12.1	0.0	0.0	260.8	60	400.1	97	260.8
1106+33.18	1108+27.18	EASTBOUND	PL	194	12.1	0.0	0.0	260.8	60	206.1	0	260.8
1108+27.18	1109+77.18	EASTBOUND	DL	150	12.1	0.0	201.7	0.0	48	312.1	75	201.7
1108+27.18	1109+77.18	EASTBOUND	PL	150	12.1	0.0	201.7	0.0	48	162.1	0	201.7
1109+77.18	1109+93.18	EASTBOUND	DL	16	12.1	21.5	0.0	0.0	10	44.1	0	21.5
1109+77.18	1109+93.18	EASTBOUND	PL	16	12.1	21.5	0.0	0.0	10	28.1	0	21.5
SUB-TOTALS						43.0 (sq. yd)	586.8 (sq. yd)	521.6 (sq. yd)	304.0 (each)	1405.6 (ft)	207.0 (each)	1151.5 (sq. yd)

						PATCH AREA			DOWEL BARS	SAW CUTS	TIE BARS	PAVEMENT FABRIC
						TYPE III 15.0" (sq. yd)	TYPE IV • (sq. yd)	TYPE IV 10.0" (sq. yd)	Z0017100 (each)	44213200 (ft)	Z0075300 (each)	44213100 (sq. yd)
FINAL TOTALS						43.0 (sq. yd)	587.0 (sq. yd)	522.0 (sq. yd)	304.0 (each)	1406.0 (ft)	207.0 (each)	1152.0 (sq. yd)

• CLASS B PATCHES, TYPE IV ARE VARIABLE DEPTH - SEE DETAIL