

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	143RS-6	CHRISTIAN	127	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	FAP 753 (IL 104) 143 RS-6		
			TOTAL QUANTITY	CONSTRUCTION TYPE CODES	
			80% FEDERAL 20% STATE	I000-2A ROADWAY	X028-2A S.N. 011-7506
42001200	PAVEMENT FABRIC	SO YD	104	104	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	51.3	51.3	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	240	240	
44000100	PAVEMENT REMOVAL	SO YD	178	178	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	37,027.0	37027	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	70990	70990	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	75.3	75.3	
44000600	SIDEWALK REMOVAL	SO FT	240	240	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	15	15	
44004250	PAVED SHOULDER REMOVAL	SO YD	279	279	
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SO YD	97	97	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	600	600	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	250	250	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	250	250	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1603	1603	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	108.2	108.2	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	72	72	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2289	2289	
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	19	19	
50105220	PIPE CULVERT REMOVAL	FOOT	1287	1123	164
50800105	REINFORCEMENT BARS	POUND	740		740
50900605	HANDRAIL REMOVAL	FOOT	40	40	
50901760	PIPE HANDRAIL	FOOT	30	30	
51205200	TEMPORARY SHEET PILING	SO FT	437		437
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERT	CU YD	11.2		11.2
54020503	PRECAST CONCRETE BOX CULVERT 5' X3' (M273)	FOOT	324		324
54207783	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 18"	FOOT	50	50	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	5	5	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2	2	
54215970	REINFORCED CONCRETE PIPE ELBOW 15"	EACH	1	1	
5421D015	PIPE CULVERT, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	28	28	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
 DATE HORIZ. CHECKED BY

PLOT DATE = Dec-12-2007 10:30:21AM
 FILE NAME = s:\projects\72624\143rs\summary.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = foughlinc1