

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	143RS-6	CHRISTIAN	127	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	FAP 753 (IL 104) 143 RS-6		
			TOTAL QUANTITY	CONSTRUCTION TYPE CODES	
			80% FEDERAL 20% STATE	I000-2A ROADWAY	X02B-2A S.N. 011-7506
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	88171.5	88171.5	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2605	2605	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	75	75	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	75	75	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	85857	85857	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	414	414	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	45	45	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	20	20	
78300100	PAVEMENT MARKING REMOVAL	SO FT	422	422	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	414	414	
X0322118	REMOVE CONCRETE FLARED END SECTION	EACH	1	1	
X0323586	PIPE DRAIN REMOVAL	FOOT	20	20	
X0324118	GRANULAR CULVERT BACKFILL	CU YD	137		137
X0324554	CONCRETE FLAT SLAB TOP	EACH	7	7	
X5012650	CONCRETE HEADWALL REMOVAL SPECIAL	EACH	2	2	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
x0325912	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT, 6"	SO YD	1534	1534	

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 DATE \_\_\_\_\_ HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_