

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	143RS-6	CHRISTIAN	127	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION	LOCATION INFO	44200101	44200144	44200148	44200150
		PAVEMENT PATCHING, TYPE IV, 8"	PAVEMENT PATCHING, TYPE II, 12"	PAVEMENT PATCHING, TYPE III, 12"	PAVEMENT PATCHING, TYPE IV, 12"
		SY	SY	SY	SY
107+20	LT - CE	34.2			
109+00	LT - CE	37.1			
111+50	LT - COMMON WEALTH AVE.	25.2			
79+67 - 414+44.77	VARIOUS - MAINLINE		600	250	250
TOTAL		96.5	600	250	250

STATION	LOCATION INFO	48101200
		AGGREGATE SHOULDERS, TYPE B
		TON
164+54 TO 193+33.46	LT/RT	177.6
197+21.23 TO 217+43	LT	62.4
197+21.23 TO 217+72	RT	63.3
225+24 TO 414+44.77	LT/RT	1167.2
348+75 TO 361+33*	LT/RT	132.9
TOTAL		1603.4

\* ADDITIONAL MATERIAL NEEDED FOR A MAXIMUM DEPTH OF 6" IN PROFILE CORRECTION AREA.

STATION	LOCATION INFO	44000157	44000198*
		HOT-MIX ASPHALT SURFACE REMOVAL, 2"	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)
		SY	SY
<b>MAINLINE</b>			
79+67 TO 148+00		18194.7	
151+50 TO 164+54		3477.3	
217+43 TO 225+24	LT	1041.3	
217+72 TO 225+24	RT	1002.7	
164+54 TO 414+44.77			65480.4
<b>SIDEROADS</b>			
94+35 TO 375.30	LT/RT (MAIN ST.)	375.3	
243+10 TO 391+70	SIDEROAD		313.0
<b>SHOULDERS</b>			
79+67 TO 148+00		10617.7	
151+50 TO 164+54		2318.2	
164+54 TO 217+72			4369.5
TOTAL		37027.2	70162.9

STATION	LOCATION INFO	MAINLINE		BACK WIDTH		LENGTH	
		SY	SY	SY	SY	SY	SY
79+67 TO 79+97				24'	30' / 5'	80.0	13.3
193+03.46 TO 193+33.46				24'	30' / 5'	80.0	13.3
197+21.23 TO 197+51.23				24'	30' / 5'	80.0	13.3
414+14.77 TO 414+44.77				24'	30' / 5'	80.0	13.3
<b>SIDEROADS</b>							
243+10 LT (KINCAID LAKE RD)				62.9'	5'	34.9	34.9
278+70 RT (TR 900 E)				102.1'	5'	56.7	56.7
281+25 (VILLA RD)				48.6'	5'	27.0	27.0
297+00 (TR 930 E)				23.4'	5'	13.0	13.0
332+45 (TR 960 E)				51.2'	5'	28.4	28.4
358+50 (TR 1025E)				18.2'	5'	10.1	10.1
384+90 (BROADUS RD)				57.3'	5'	31.8	31.8
391+70 (TR 1085 E)				25.9'	5'	14.4	14.4
TOTAL						536.4	269.6

\* SEE ENTRANCE AND MAILBOX SCHEDULE FOR ADDITIONAL QUANTITIES.

NOTE: BUTT JOINT AREA NOT INCLUDED IN THIS SCHEDULE.  
\* SEE STRUCTURE SCHEDULES FOR ADDITIONAL QUANTITIES.

STATION	LOCATION INFO	70301000****	70300100	70300230	78100100	78300200	78001120
		WORK-ZONE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKINGS	TEMPORARY PAVEMENT MARKING LINE 5"	RAISED REFLECTIVE PAVEMENT MARKER 80' / REF	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAINT PAVEMENT MARKING LINE 5"
		SF	FOOT	FOOT	EACH	EACH	FOOT
<b>MAINLINE</b>							
79+67 TO 414+44.77* / ***	YELLOW - SKIP DASH WHITE - EDGE LINES	1,086.7	9,822.0	8,185.5			7,269.0
215+70 TO 294+90	YELLOW - NO PASSING**			9,504.0			9,504.0
382+55 TO 389+39				1,900.0			1,900.0
79+67 TO 193+33.46***					137	137	
197+21.23 TO 414+44.77					272	272	
<b>SHOULDERS (WHERE SHOULDERS ARE 4' OR WIDER)</b>							
79+67 TO 94+10	LT/RT	38.5	346.3				
125+39 TO 130+37	LT/RT	13.3	119.5				
130+37 TO 181+91.81***	LT/RT	132.8	1,195.2				
207+01.16 TO 217+43	LT	13.9	125.0				
207+01.16 TO 217+72	RT	14.3	128.5				
TOTALS		1,299.4	11,736.6	85,069.5	409	409	84,853.0

\* OMIT STRUCTURE STA. 193+33.46 TO STA. 197+21.23  
\*\* CONFIRM LENGTHS WITH OPERATIONS BEFORE STRIPING  
\*\*\* QUANTITIES FOR STA. 148+50 TO STA. 151+50 ARE IN STRUCTURE REPLACEMENT SCHEDULES  
\*\*\*\* SEE STRUCTURE SCHEDULES FOR ADDITIONAL QUANTITIES.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES

SCALE: VERT. / HORIZ.  
DATE: / / DRAWN BY: / CHECKED BY: /