

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	3
STA. 2302+44.00		TO STA. 2364+17.00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* 7810 & 7825 (IL 96)

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	1000-2A	
<i>URBAN</i>						
X6050700	REMOVE INLET BOX	EACH	1	1		
20200100	EARTH EXCAVATION	CU YD	34	34		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	62	62		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	7.7	7.7		
20400800	FURNISHED EXCAVATION	CU YD	28	28		
28100107	STONE RIPRAP, CLASS A4	SO YD	115	115		
28200200	FILTER FABRIC	SO YD	115	115		
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SO YD	23	23		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.7	13.7		
40600300	AGGREGATE (PRIME COAT)	TON	64	64		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,550	1,319	184	47
40600990	TEMPORARY RAMP	SO YD	272	118	122	32
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NTO	TON	3,391	2,437	738	216
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	128	128		
44000100	PAVEMENT REMOVAL	SO YD	17	17		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	29,899	21,615	6,403	1,881
44000400	GUTTER REMOVAL	FOOT	98	98		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	70	70		
44002500	GUTTER OUTLET REMOVAL	EACH	1	1		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	45	45		
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	45	45		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	162	162		
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SO YD	44	44		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	222	222		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
54200649	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	9	9		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1		
54248515	CONCRETE COLLAR	EACH	2	2		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	5	5		
60218300	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24	FOOT	50	50		
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24 (SPECIAL)	FOOT	117	117		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	200	200		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	1000-2A
<i>URBAN</i>						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,088	1,477	461	150
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	755	425	283	47
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	19,809	15,039	3,426	1,344
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,833	1,529	1,154	150
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	808	250	435	123
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	374	204	144	26
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	348	246	77	25
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	19,809	15,039	3,426	1,344
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	808	250	435	123
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	755	425	283	47
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	2,833	1,529	1,154	150
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24	FOOT	374	204	144	26
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	319	198	92	29
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	8	8		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	184	184		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	5035	2,737	1,650	648
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4		2	2

\* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
F.A.U. Route 7810 & 7825 (IL 96)  
Section 11RS-8  
ADAMS COUNTY

SCALE: VERT. DATE: JUNE 11, 2007  
DRAWN BY: JWC  
CHECKED BY: RSC

PLOT DATE : Nov-02-2007 09:14:27PM  
 FILE NAME : c:\projects\650605\SHTSUMMARY.DGN  
 PLOT SCALE : 1/8"=1'-0" / 1/4"  
 USER NAME : laughton1