

CONTRACT NO. 72943

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	18
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 7810 & 7825 (IL 96)				

SCHEDULE OF QUANTITIES

AGGREGATE SHOULDERS, TYPE B

LOCATION	QUANTITY (TON)
F. A. P. 7810 (IL 96)	
STA. 2302+44.00 to STA. 2304+11.00	9.51
STA. 2310+20.00 to STA. 2329+31.00	108.82
STA. 2329+31.00 to STA. 2331+20.00 RT	5.38
STA. 2336+68.00 to STA. 2342+80.00 RT	17.43
BRIDGE OMISSION (S. N. 001-0033)	
STA. 2345+64.20 to STA. 2345+96.20	
STA. 2348+40.00 to STA. 2354+59.00	35.25
STA. 2354+59.00 to STA. 2355+16.00 LT	1.62
SUBTOTAL	178.01
(Subtract Side Roads & Entrances)	-16.81
PROJECT TOTAL	162

CONCRETE COLLAR

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2312+37.37 RT	1
STA. 2324+85.00 RT	1
PROJECT TOTAL	2

STORM SEWERS, CLASS A, TYPE 1 24"

LOCATION	QUANTITY (FOOT)
F. A. U. 7810 (IL 96)	
(Measured Using CADD)	
STA. 2324+85.00 RT	4.68
PROJECT TOTAL	5

PIPE CULVERTS, TYPE 1, CORRUGATED

STEEL OR ALUMINUM CULVERT PIPE 24"

LOCATION	QUANTITY (FOOT)
F. A. U. 7810 (IL 96)	
STA. 2312+32.00 to STA. 2312+35.21 RT	5.53
Added for Possible Field Adjustment	3.0
PROJECT TOTAL	9

PRECAST REINFORCED CONCRETE FLARED

END SECTIONS 24"

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2324+85.00 RT	1
PROJECT TOTAL	1

COMBINATION CURB & GUTTER REMOVAL

LOCATION	QUANTITY (FOOT)
F. A. U. 7810 (IL 96)	
STA. 2338+49.70 to STA. 2339+19.00 LT	69.30
PROJECT TOTAL	70

MANHOLES, TYPE A, 4' DIAMETER,

TYPE 1 FRAME OPEN LID

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2312+30.37, 18.58' RT	1
PROJECT TOTAL	1

GRATING FOR CONCRETE FLARED END

SECTION 24"

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2324+85.00 RT	1
PROJECT TOTAL	1

GUTTER OUTLET REMOVAL

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2340+16.30 to STA. 2340+46.00 LT	1
PROJECT TOTAL	1

CONCRETE HEADWALL REMOVAL

LOCATION	QUANTITY (EACH)
F. A. U. 7810 (IL 96)	
STA. 2324+85.00 RT	1
PROJECT TOTAL	1

PAVEMENT REMOVAL

LOCATION	QUANTITY (SQ YD)
F. A. U. 7810 (IL 96)	
STA. 2338+49.70 to STA. 2339+19.00	5.87
STA. 2340+16.30 to STA. 2340+46.00	10.66
PROJECT TOTAL	17

LEGEND

(#) QUANTITY DESIGNATED FOR CITY OF QUINCY
 [#] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.U. Route 7810 & 7825 (IL 96)
 Section 11RS-8
 ADAMS COUNTY

SCALE: VERT. DRAWN BY: JWC
 HORIZ. CHECKED BY: RSC
 DATE: NOVEMBER 28, 2005

Rev.