

CONTRACT NO. 72943  
• 7810 & 7825 (IL 96)

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**SHORT-TERM PAVEMENT MARKING**

LOCATION	QUANTITY (FOOT)
<i>(After Milling):</i>	
F. A. U. 7810 ( IL 96)	
STA. 2302+44.00 to STA. 2306+72.00	77.8
STA. 2305+20.00 to STA. 2306+72.00	13.8
STA. 2307+55.00 to STA. 2309+07.00	13.8
STA. 2309+07.00 to STA. 2311+77.00	49.1
STATE ST.	
STA. 10+47.00 to STA. 11+99.00 [COUNTY]	[ 27.6 ]
STA. 11+99.00 to STA. 14+60.00 [COUNTY]	[ 47.5 ]
36TH ST.	
STA. 100+42.11 to STA. 105+15.00 (CITY)	( 129 )
F. A. U. 7810 ( IL 96)	
STA. 2311+77.00 to STA. 2329+10.00	157.5
STA. 2329+10.00 to STA. 2330+20.00	20
STA. 2330+20.00 to STA. 2330+80.00	10.9
STA. 2331+35.00 to STA. 2333+24.00	34.4
30TH ST.	
STA. 104+64.00 to STA. 105+54.80 (CITY)	( 8.3 )
STA. 104+64.00 to STA. 105+64.10 (CITY)	( 9.1 )
S. LEG	2.2
F. A. U. 7810 ( IL 96)	
STA. 2334+10.00 to STA. 2335+62.00	27.6
STA. 2335+62.00 to STA. 2337+87.00	40.9
STA. 2337+87.00 to STA. 2356+46.00	169
STA. 2356+46.00 to STA. 2358+76.00	41.8
STA. 2358+76.00 to STA. 2360+28.00	27.6
F. A. U. 7825 ( IL 96)	
STA. 2361+19.00 to STA. 2362+71.00	27.6
STA. 2362+71.00 to STA. 2364+17.00	26.5
STATE ST.	
STA. 31+25.00 to STA. 32+57.00 (CITY)	( 24 )
STA. 32+57.00 to STA. 33+59.00 (CITY)	( 27.8 )
24TH ST.	
STA. 4+50.00 to STA. 5+52.00 (CITY)	( 18.6 )
STA. 5+52.00 to STA. 6+78.00 (CITY)	( 11.5 )
<b>SUBTOTAL (*1) (AFTER MILLING)</b>	<b>1,043.9</b>

**SCHEDULE OF QUANTITIES**

**SHORT-TERM PAVEMENT MARKING (cont.)**

LOCATION	QUANTITY (FOOT)
<b>SUBTOTAL (*2) (AFTER SURF. CSE)</b>	<b>1,043.9</b>
<b>PROJECT TOTAL</b>	<b>2,088</b>
80 FED / 20 STATE	1,477
(CITY)	(461)
[COUNTY]	[150]

**WORK ZONE PAVEMENT MARKING REMOVAL**

LOCATION	QUANTITY (SQ FT)
<i>(Removal of Short-Term Pavement Marking)</i>	
(After Surface Course)	347.97
<b>PROJECT TOTAL</b>	<b>348</b>
80 FED / 20 STATE	246
(CITY)	(77)
[COUNTY]	[25]

**COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)**

LOCATION	QUANTITY (FOOT)
F. A. U. 7810 ( IL 96)	
STA. 2338+49.70 to STA. 2339+66.50 LT	116.80
<b>PROJECT TOTAL</b>	<b>117</b>

**PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS & SYMBOLS**

LOCATION	WHITE (SQ FT)
WHITE	
F. A. U. 7810 ( IL 96)	
STA. 2305+20.00 - LT TURN ARROW	15.6
STA. 2305+83.50 - LT TURN ARROW	15.6
STA. 2306+47.00 - LT TURN ARROW	15.6
STATE ST.	
STA. 10+72.00 - LT TURN ARROW [COUNTY]	[ 15.6 ]
STA. 11+35.50 - LT TURN ARROW [COUNTY]	[ 15.6 ]
STA. 11+99.00 - LT TURN ARROW [COUNTY]	[ 15.6 ]
36TH ST.	
STA. 100+71.35 - LT TURN ARROW (CITY)	( 15.6 )
RT TURN ARROW (CITY)	( 15.6 )
STA. 101+34.45 - LT TURN ARROW (CITY)	( 15.6 )
RT TURN ARROW (CITY)	( 15.6 )
STA. 101+97.82 - LT TURN ARROW (CITY)	( 15.6 )
RT TURN ARROW (CITY)	( 15.6 )
STA. 104+97.36 - RT TURN ARROW (CITY)	( 15.6 )
STA. 105+44.67 - RT TURN ARROW (CITY)	( 15.6 )
F. A. U. 7810 ( IL 96)	
STA. 2307+80.00 - LT TURN ARROW	15.6
THROUGH ARROW	11.5
RT TURN ARROW	15.6
STA. 2308+43.50 - LT TURN ARROW	15.6
THROUGH ARROW	11.5
RT TURN ARROW	15.6
STA. 2309+07.00 - LT TURN ARROW	15.6
THROUGH ARROW	11.5
RT TURN ARROW	15.6
<b>SUBTOTAL (*1)</b>	<b>346.5</b>

**LEGEND**

( # ) QUANTITY DESIGNATED FOR CITY OF QUINCY  
[ # ] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
F.A.U. Route 7810 & 7825 (IL 96)  
Section 11RS-8  
ADAMS COUNTY

SCALE: VERT.  
HORIZ.  
DATE: NOVEMBER 28, 2006

DRAWN BY: JWC  
CHECKED BY: RSC

PLOT DATE = Nov-22-2007 01:14:56PM  
FILE NAME = c:\projects\650605\shsch.dgn  
PLOT SCALE = 1/8"=1'-0" / IN.  
USER NAME = laughlin-1