

CONTRACT NO. 72943

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 7810 & 7825 (IL 96)				

PREFORMED PLASTIC PAVEMENT
MARKING-LETTERS AND SYMBOLS (cont.)

LOCATION	WHITE (SQ FT)
WHITE	
F. A. U. 7810 (IL 96) (cont.)	
STA. 2330+20.00 - LT TURN ARROW	15.6
STA. 2330+65.00 - LT TURN ARROW	15.6
STA. 2331+35.00 - LT TURN ARROW	15.6
STA. 2332+17.00 - LT TURN ARROW	15.6
STA. 2332+99.00 - LT TURN ARROW	15.6
30TH ST.	
STA. 105+23.60 - COMB. LT TURN & THROUGH ARROW (CITY)	(26)
RT TURN ARROW (CITY)	(15.6)
F. A. U. 7810 (IL 96)	
STA. 2334+35.00 - LT TURN ARROW	15.6
STA. 2334+98.50 - LT TURN ARROW	15.6
STA. 2335+62.00 - LT TURN ARROW	15.6
STA. 2342+47.00 - RT TURN ARROW	15.6
STA. 2344+00.00 - RT TURN ARROW	15.6
STA. 2358+76.00 - LT TURN ARROW	15.6
STA. 2359+39.50 - LT TURN ARROW	15.6
STA. 2360+03.00 - LT TURN ARROW	15.6
F. A. U. 7825 (IL 96)	
STA. 2361+44.00 - LT TURN ARROW	15.6
STA. 2362+07.50 - LT TURN ARROW	15.6
STA. 2362+71.00 - LT TURN ARROW	15.6
STATE ST.	
STA. 32+57.00 - LT TURN ARROW (CITY)	(15.6)
THROUGH ARROW (CITY)	(11.5)
RT TURN ARROW (CITY)	(15.6)
STA. 33+34.00 - LT TURN ARROW (CITY)	
THROUGH ARROW (CITY)	(11.5)
RT TURN ARROW (CITY)	(15.6)
24TH ST.	
STA. 4+75.00 - LT TURN ARROW (CITY)	(15.6)
STA. 5+52.00 - LT TURN ARROW (CITY)	(15.6)
SUBTOTAL (*2)	407.8
PROJECT TOTAL	755
80 FED / 20 STATE	425
(CITY)	(283)
[COUNTY]	[47]

SCHEDULE OF QUANTITIES

PREFORMED PLASTIC PAVEMENT
MARKING, TYPE B - LINE 24"

LOCATION	WHITE SOLID (FOOT)
F. A. U. 7810 (IL 96)	
(Measured Using CADD)	
(STOP BAR)	
STA. 2306+72.00	32
STATE ST.	
STA. 10+47.00 [COUNTY]	[26]
36TH ST.	
STA. 100+42.41 (CITY)	(28.6)
STA. 100+53.14 (CITY)	(11)
F. A. U. 7810 (IL 96)	
STA. 2307+55.00	40
STA. 2333+24.00	28
30TH ST.	
STA. 105+54.80 (CITY)	(13.3)
STA. 105+64.10 (CITY)	(20.9)
S. LEG (Measured Using CADD)	19
F. A. U. 7810 (IL 96)	
STA. 2334+10.00	24.5
STA. 2360+28.00	33.6
F. A. U. 7825 (IL 96)	
STA. 2361+19.00	14.8
STA. 2361+21.00	12.5
STATE ST.	
STA. 33+59.00 (CITY)	(37.6)
24TH ST.	
STA. 4+50.00 (CITY)	(32.2)
PROJECT TOTAL	374
80 FED / 20 STATE	204
(CITY)	(144)
[COUNTY]	[26]

LEGEND

(#) QUANTITY DESIGNATED FOR CITY OF QUINCY
[#] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
F.A.U. Route 7810 & 7825 (IL 96)
Section 11RS-8
ADAMS COUNTY

SCALE: VERT.
HORIZ.
DATE: NOVEMBER 28, 2006

DRAWN BY: JWC
CHECKED BY: RSC

PLOT DATE = Nov-28-2007 01:44:37PM
FILE NAME = c:\projects\650605\shsch.dgn
PLOT SCALE = 1/8"=1'-0"
USER NAME = laughlin