

CONTRACT NO. 72943

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 7810 & 7825 (IL 96)				

SCHEDULE OF QUANTITIES

PAVEMENT SCHEDULE (#2 OF 3)									
LOCATION STATION TO STATION	COUNTY OR CITY	LENGTH (FT)	EXIST PAVEMENT WIDTH (FT)	HMA SURF THICKNESS (IN)	HMA SURF REMOVAL BUTT - JOINT (SQ YD)	HMA SURF REMOVAL 2" (SQ YD)	HMA CONC SURF CSE "D" N70 (TON)	BIT MAT PRIME COAT (TON)	AGG PRIME COAT (TON)
(30th St.)		-	-	-	-	-	-	-	-
STA. 104+64.00 TO STA. 104+74.00	(CITY)	10.00	38	2	(42.22)	-	-	(0.02)	(0.08)
STA. 104+64.00 TO STA. 105+80.00	(CITY)	116.00	38	2	-	-	(54.86)	-	-
STA. 104+74.00 TO STA. 105+80.00	(CITY)	106.00	38	2	-	(447.56)	-	(0.17)	(0.90)
STA. 104+79.00 TO STA. 105+80.00	(CITY)	101.00	38	2	-	-	-	-	-
(Intersection of IL 96/30th St.)		-	-	-	-	-	-	-	-
(Measured Using CADD)		-	-	-	-	-	-	-	-
S. Leg		-	-	2	36.03	140.05	19.72	0.07	0.35
N. E. Quadrant	(CITY)	-	-	2	-	(45.94)	(5.15)	(0.02)	(0.09)
N. W. Quadrant	(CITY)	-	-	2	-	(48.43)	(5.42)	(0.02)	(0.10)
F. A. U. 7810 (IL 96)		-	-	-	-	-	-	-	-
STA. 2336+68.00 TO STA. 2338+49.70		181.70	Var fr. 40 TO 24	2	-	646.04	72.36	0.25	1.29
STA. 2338+49.70 TO STA. 2340+46.00		196.30	24	2	-	523.47	58.63	0.20	1.05
STA. 2340+46.00 TO STA. 2341+97.80		151.80	26	2	-	438.53	49.12	0.17	0.88
STA. 2341+97.80 TO STA. 2344+41.00		243.20	34	2	-	918.76	102.90	0.35	1.84
STA. 2344+41.00 TO STA. 2345+34.20		93.20	26	2	-	269.24	-	0.10	0.54
STA. 2345+34.20 TO STA. 2345+54.20		20.00	32	2	-	71.11	-	0.03	0.14
STA. 2344+41.00 TO STA. 2345+64.20		123.20	26	2	-	-	39.86	-	-
STA. 2345+54.20 TO STA. 2345+64.20		10.00	32	2	35.56	-	-	0.01	0.07
BRIDGE OMISSION (S. N. 068-0026) STA. 2345+64.20 to STA. 2345+96.20									
STA. 2345+96.20 TO STA. 2346+06.20		10.00	32	2	35.56	-	-	0.01	0.07
STA. 2345+96.20 TO STA. 2354+09.00		812.80	26	2	-	-	262.99	-	-
STA. 2346+06.20 TO STA. 2346+26.20	RT	20.00	3	2	-	6.67	-	0.003	0.01
STA. 2346+06.20 TO STA. 2346+30.00	LT	23.80	3	2	-	7.93	-	0.003	0.02
STA. 2346+06.20 TO STA. 2354+09.00		802.80	26	2	-	2,319.20	-	0.88	4.64
STA. 2354+09.00 TO STA. 2354+59.00		50.00	Var fr. 26 TO 24	2	-	138.89	15.56	0.05	0.28
STA. 2354+59.00 TO STA. 2355+79.30		120.30	24	2	-	320.80	35.93	0.12	0.64
STA. 2355+79.30 TO STA. 2357+68.00		188.70	Var fr. 24 TO 40	2	-	670.93	75.14	0.25	1.34
STA. 2357+68.00 TO STA. 2360+76.77		308.77	40	2	-	1,372.31	153.70	0.52	2.74
F. A. U. 7825 (IL 96)		-	-	-	-	-	-	-	-
STA. 2360+94.27 TO STA. 2363+08.10		213.83	40	2	-	950.36	106.44	0.36	1.90
STA. 2363+08.10 TO STA. 2364+07.00		98.90	Var fr. 40 TO 35.5	2	-	414.83	-	0.16	0.83
STA. 2363+08.10 TO STA. 2364+17.00		108.90	Var fr. 40 TO 35.5	2	-	-	51.16	-	-
STA. 2364+07.00 TO STA. 2364+17.00		10.00	35.5	2	39.44	-	-	0.01	0.08
		-	-	-	-	-	-	-	-
SUBTOTAL (*2)					188.81	9,751.05	1,108.94	3.78	19.88

LEGEND

(#) QUANTITY DESIGNATED FOR CITY OF QUINCY
 [#] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.U. Route 7810 & 7825 (IL 96)
 Section 11RS-8
 ADAMS COUNTY

SCALE: VERT. DRAWN BY: JWC
 HORIZ. CHECKED BY: RSC
 DATE: NOVEMBER 28, 2006

PLOT DATE = Nov-22-2007 01:14:40PM
 FILE NAME = c:\projects\6550605\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1