

CONTRACT NO. 72943

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	11RS-8	ADAMS	64	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 7810 & 7825 (IL 96)				

SCHEDULE OF QUANTITIES

PAVEMENT SCHEDULE (#3 OF 3)									
LOCATION STATION TO STATION	COUNTY OR CITY	LENGTH (FT)	EXIST PAVEMENT WIDTH (FT)	HMA SURF THICKNESS (IN)	HMA SURF REMOVAL BUTT - JOINT (SQ YD)	HMA SURF REMOVAL 2" (SQ YD)	HMA CONC SURF CSE "D" N70 (TON)	BIT MAT PRIME COAT (TON)	AGG PRIME COAT (TON)
F. A. P. 7825 (IL 96)									
(State St.)									
STA. 31+10.00 TO STA. 31+20.00	(CITY)	10.00	37	2	(41.11)	-	-	(0.02)	(0.08)
STA. 31+10.00 TO STA. 31+79.00	(CITY)	69.00	37	2	-	-	(31.77)	-	-
STA. 31+20.00 TO STA. 31+79.00	(CITY)	59.00	37	2	-	(242.56)	-	(0.09)	(0.49)
STA. 31+79.00 TO STA. 32+60.00	(CITY)	81.00	Var fr. 37 TO 49	2	-	(387)	(43.34)	(0.15)	(0.77)
STA. 32+60.00 TO STA. 34+00.00	(CITY)	140.00	49	2	-	(762.22)	(85.37)	(0.29)	(1.52)
(24th. St.)									
STA. 4+22.50 TO STA. 5+52.10	(CITY)	129.60	45	2	-	(648.00)	(72.58)	(0.25)	(1.30)
STA. 5+52.10 TO STA. 6+68.00	(CITY)	115.90	Var fr. 45 TO 42	2	-	(560.18)	-	(0.21)	(1.12)
STA. 5+52.10 TO STA. 6+78.00	(CITY)	125.90	Var fr. 45 TO 42	2	-	-	(68.15)	-	-
STA. 6+68.00 TO STA. 6+78.00	(CITY)	10.00	42	2	(46.67)	-	-	(0.02)	(0.09)
(Intersection of IL96/State St./24th. St.)									
(Measured Using CADD)									
N. W. Quadrant	(CITY)	-	-	2	-	(51.17)	(5.73)	(0.02)	(0.10)
N. E. Quadrant		-	-	2	-	15.65	1.75	0.01	0.03
S. W. Quadrant	(CITY)	-	-	2	-	(86.33)	(9.67)	(0.03)	(0.17)
S. E. Quadrant	(CITY)	-	-	2	-	(19.21)	(2.15)	(0.01)	(0.04)
Incidental HMA Surfacing (HMA P. E. 's & CE 'S) (SQ YD)									
Incidental HMA Surfacing (HMA Side Roads) (SQ YD)									
HMA Shoulders 2" (SQ YD)									
HMA Shoulders 8" (SQ YD)									
SUBTOTAL (*3)					1, 227. 78	2, 772. 32	320. 51	3. 08	8. 57
PROJECT TOTAL					1, 550	29, 899	3, 391	13. 7	65
80 FED / 20 STATE					1, 319	21, 615	2, 437	10. 3	47
(CITY)					(184)	(6, 403)	(738)	(2. 5)	(13)
[COUNTY]					[47]	[1, 881]	[216]	[0. 9]	[5]

LEGEND

(#) QUANTITY DESIGNATED FOR CITY OF QUINCY
[#] QUANTITY DESIGNATED FOR ADAMS COUNTY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.U. Route 7810 & 7825 (IL 96)
Section 11RS-8
ADAMS COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE: NOVEMBER 28, 2006

DRAWN BY: JWC
CHECKED BY: RSC

PLOT DATE = Nov-28-2007 08:14:40PM
 FILE NAME = c:\projects\650605\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1