

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320		LOGAN	12	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

D-6 SHLDR RUMBLE STRIPS 2008-4

EXCAVATING AND GRADING EXISTING SHOULDER SCHEDULE					
LOCATION STATION TO STATION		TOTAL LENGTH (FT)	SEE NOTE 1 LENGTH (FT)	LENGTH (UNIT)	
FAP 320 (IL 121)					
RT. STA. 323+14.00	TO RT. STA. 345+00.00	2186.0	2079.0	20.8	
LT. STA. 323+14.00	TO LT. STA. 345+00.00	2186.0	2075.0	20.8	
RT. STA. 345+00.00	TO RT. STA. 376+42.00	3142.0	3025.5	30.3	
LT. STA. 345+00.00	TO LT. STA. 376+42.00	3142.0	3096.5	31.0	
RT. STA. 376+42.00	TO RT. STA. 403+43.00	2701.0	2596.5	26.0	
LT. STA. 376+42.00	TO LT. STA. 403+43.00	2701.0	2608.5	26.1	
RT. STA. 403+43.00	TO RT. STA. 438+91.40	3548.4	3222.4	32.2	
LT. STA. 403+43.00	TO LT. STA. 438+91.40	3548.4	3501.4	35.0	
STA. EQ. 438+91.4 BK. = STA. 434+30.10 AH.					
RT. STA. 434+30.10	TO RT. STA. 439+20.00	489.9	489.9	4.9	
LT. STA. 434+30.10	TO LT. STA. 439+20.00	489.9	401.9	4.0	
RT. STA. 439+20.00	TO RT. STA. 443+90.00	470.0	-	-	
LT. STA. 439+20.00	TO LT. STA. 443+90.00	470.0	-	-	
TOTAL		25,074.6	23,096	231.0	

HOT-MIX ASPHALT SHOULDERS, 8" SCHEDULE					
LOCATION STATION TO STATION		PROP. BIT. SHOULDERS WIDTH (FT)	TOTAL LENGTH (FT)	SEE NOTE 1 LENGTH (FT)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)
FAP 320 (IL 121)					
RT. STA. 323+14.00	TO RT. STA. 345+00.00	3	2186.0	2079.0	693.0
LT. STA. 323+14.00	TO LT. STA. 345+00.00	3	2186.0	2075.0	691.7
RT. STA. 345+00.00	TO RT. STA. 376+42.00	3	3142.0	3025.5	1008.5
LT. STA. 345+00.00	TO LT. STA. 376+42.00	3	3142.0	3096.5	1032.2
RT. STA. 376+42.00	TO RT. STA. 403+43.00	3	2701.0	2596.5	865.5
LT. STA. 376+42.00	TO LT. STA. 403+43.00	3	2701.0	2608.5	869.5
RT. STA. 403+43.00	TO RT. STA. 438+91.40	3	3548.0	3222.4	1074.1
LT. STA. 403+43.00	TO LT. STA. 438+91.40	3	3548.0	3501.0	1167.0
STA. EQ. 438+91.4 BK. = STA. 434+30.10 AH.					
RT. STA. 434+30.10	TO RT. STA. 439+20.00	3	489.9	489.9	163.3
LT. STA. 434+30.10	TO LT. STA. 439+20.00	3	489.9	401.9	134.0
RT. STA. 439+20.00	TO RT. STA. 443+90.00	-	470.0	-	-
LT. STA. 439+20.00	TO LT. STA. 443+90.00	-	470.0	-	-
TOTAL			25,074.6	23096	7,699

SHOULDER RUMBLE STRIP SCHEDULE					
LOCATION STATION TO STATION		SHOULDERS	TOTAL LENGTH (FT)	SEE NOTE 1 LENGTH (FT)	
FAP 320 (IL 121)					
RT. STA. 323+14.00	TO RT. STA. 345+00.00	PROP.	2186.0	2,072.5	
LT. STA. 323+14.00	TO LT. STA. 345+00.00	PROP.	2186.0	2,065.0	
RT. STA. 345+00.00	TO RT. STA. 376+42.00	PROP.	3142.0	3,020.0	
LT. STA. 345+00.00	TO LT. STA. 376+42.00	PROP.	3142.0	3,093.5	
RT. STA. 376+42.00	TO RT. STA. 403+43.00	PROP.	2701.0	2,588.0	
LT. STA. 376+42.00	TO LT. STA. 403+43.00	PROP.	2701.0	2,602.5	
RT. STA. 403+43.00	TO RT. STA. 438+91.40	PROP.	3548.0	3,201.9	
LT. STA. 403+43.00	TO LT. STA. 438+91.40	PROP.	3548.0	3498.0	
STA. EQ. 438+91.4 BK. = STA. 434+30.10 AH.					
RT. STA. 434+30.10	TO RT. STA. 439+20.00	PROP.	489.9	489.9	
LT. STA. 434+30.10	TO LT. STA. 439+20.00	PROP.	489.9	394.9	
RT. STA. 439+20.00	TO RT. STA. 443+90.00	EXIST.	470.0	447.0	
LT. STA. 439+20.00	TO LT. STA. 443+90.00	EXIST.	470.0	431.0	
TOTAL			25,074.6	23,904	

AGGREGATE SHOULDERS, TYPE B SCHEDULE					
LOCATION STATION TO STATION		AGGREGATE SHOULDERS WIDTH (FT)	TOTAL LENGTH (FT)	SEE NOTE 1 LENGTH (FT)	AGGREGATE SHOULDERS, TYPE B (TON)
FAP 320 (IL 121)					
RT. STA. 323+14.00	TO RT. STA. 345+00.00	3	2186.0	2085.5	118.8
LT. STA. 323+14.00	TO LT. STA. 345+00.00	3	2186.0	2085.0	118.8
RT. STA. 345+00.00	TO RT. STA. 376+42.00	3	3142.0	3035.5	172.9
LT. STA. 345+00.00	TO LT. STA. 376+42.00	3	3142.0	3102.5	176.7
RT. STA. 376+42.00	TO RT. STA. 403+43.00	3	2701.0	2613.5	148.8
LT. STA. 376+42.00	TO LT. STA. 403+43.00	3	2701.0	2620.5	149.2
RT. STA. 403+43.00	TO RT. STA. 438+91.40	3	3548.0	3263.9	185.9
LT. STA. 403+43.00	TO LT. STA. 438+91.40	3	3548.0	3507.4	199.7
STA. EQ. 438+91.4 BK. = STA. 434+30.10 AH.					
RT. STA. 434+30.10	TO RT. STA. 439+20.00	3	489.9	489.9	27.9
LT. STA. 434+30.10	TO LT. STA. 439+20.00	3	489.9	413.9	23.6
RT. STA. 439+20.00	TO RT. STA. 443+90.00	3	470.0	450.0	25.6
LT. STA. 439+20.00	TO LT. STA. 443+90.00	3	470.0	434.4	24.7
TOTAL			25074.6	24101.6	1373.0

PLT FILE : No-15-2007-07-21-14  
 FILE NAME : 070807-07-21-14.dgn  
 PLOT SCALE : 1/8"=1'-0"  
 USER NAME : jaughlin

NOTE  
 1. LENGTHS HAVE BEEN ADJUSTED FOR INTERSECTION AND ENTRANCE OMISSIONS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES OF QUANTITIES FAP 320 (IL 121) SECT. D-6 SHLDR RUMBLE STRIPS 2008-4 LOGAN COUNTY

SCALE: VERT. HORIZ.  
 DATE: DRAWN BY: CHECKED BY: