

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1832	5BR-2	WASHINGTON	97	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS					OVER 15 UNITS							
1450+57.90	32.5	LT				12									
1450+63.50	30.4	LT			10										
1450+63.50	30.3	LT				12									
1450+63.70	28.7	LT			10										
1450+65.90	32.9	LT	6												
1450+82.69	31.2	LT							20						
1450+98.04	31.3	LT				12									
1451+05.00	32.5	LT			10										
1451+08.90	32.8	LT	6												
1451+12.00	28.1	LT					15								
1451+13.30	28.0	LT					15								
1451+29.70	30.1	LT			10										
1451+38.80	34.2	LT					15								
1451+39.67	42.4	LT										36			
1451+40.50	34.8	LT						24							
1451+51.60	46.3	LT							30						
1451+53.20	31.5	LT			10										
1451+53.77	44.1	LT		8											
1451+54.67	31.9	LT						24							
1451+62.24	41.5	LT							30						
1451+63.48	34.5	LT						24							
1451+68.40	33.1	LT	6												
1451+71.60	33.8	LT			10										
1451+73.03	42.3	LT						18							
1451+80.05	34.9	LT	6												
1451+80.90	33.0	LT	6												
1451+84.40	37.0	LT										36			
1451+85.70	28.6	LT						18							
1452+01.20	41.0	LT		8											
1452+03.85	45.4	LT		8											
1452+16.90	38.9	LT										36			
1452+18.40	30.1	LT					18								
1452+19.17	31.3	LT					18								
1452+19.86	30.8	LT							24						
1452+20.50	46.5	LT	6												
1452+22.70	44.7	LT		8											
1452+27.89	46.4	LT		8											
1452+35.77	40.0	LT				15									
1452+36.50	42.2	LT							24						
1452+40.80	44.0	LT	6												
1452+48.92	39.5	LT	6												
1452+51.23	42.0	LT		8											
1452+53.86	40.2	LT		8											
1452+55.64	36.1	LT							24						
1452+62.53	49.4	LT	6												
1452+66.71	47.5	LT	6												
1452+75.03	31.4	LT			10										
1452+75.60	32.5	LT	6												
1452+81.28	46.7	LT			10										
1452+98.54	26.3	LT		8											
1452+99.00	26.2	LT	6												
1454+04.19	33.3	LT										44			
1454+04.64	30.8	LT				15									
1454+06.74	32.6	LT							24						
1454+13.04	31.0	LT	6												
1454+19.94	33.3	LT					18								
1456+85.80	33.0	LT				15									
1457+23.60	30.3	LT											50		
1457+43.90	34.1	LT		8											
SUB-TOTAL			78	72	80	36	90	90	20	168	60	108	44	50	
TOTAL						356							540		

SEEDING SCHEDULE

STA	STA	AREA (SQ FT)	SEEDING CLASS 2 (ACRE)	SEEDING CLASS 1 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
1449+25.00 TO	1457+50.00 LT	6370	0.15		13.16	13.16	13.16	0.15
1449+25.00 TO	1452+79.50 RT	2952		0.1	6.10	6.10	6.10	0.07
1455+92.00 TO	1458+00.00 RT	2113		0.1	4.37	4.37	4.37	0.05
1449+25.00 TO	1457+50.00 RT	9568	0.22		19.77	19.77	19.77	0.22
TOTAL			0.37	0.20	43.40	43.40	43.40	0.49

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1449+25.00 TO STA. 1452+79.50	197.3	147.9	668.1	-520.2
STA. 1453+43.50 TO STA. 1457+50.00	401.3	301.0	435.0	-134.1
TOTAL	598.6	448.9	1103.1	-654.3

EARTHWORK SCHEDULE (WIDENING)

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJTD FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA. 1449+25.00 TO STA. 1452+83.00	30.5	22.9	0.0	22.9
STA. 1453+47.00 TO STA. 1457+50.00	34.3	25.7	0.0	25.7
TOTAL	64.8	48.6	0.0	48.6

ROW MARKERS SCHEDULE

STATION	LOCATION		ROW MARKERS (EA)
	SIDE	OFFSET	
1449+00.00	29.11	L+	1
1449+00.00	30.89	R+	1
1449+50.00	50.89	R+	1
1450+00.00	39.11	L+	1
1451+00.00	39.12	L+	1
1451+50.00	54.13	L+	1
1453+00.00	54.14	L+	1
1453+50.00	39.14	L+	1
1457+50.00	50.83	R+	1
1458+00.00	30.83	R+	1
1458+00.00	39.17	L+	1
1458+00.00	29.17	L+	1
TOTAL			12

S.N. 095-0077

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAS ROUTE 1832
 SECTION 5BR-2
 WASHINGTON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____