

# SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES |   |        | 100% STATE       | CONSTRUCTION TYPE CODE |  |  | SUMMARY OF QUANTITIES |  |       | 100% STATE       | CONSTRUCTION TYPE CODE |  |  |
|-----------------------|---|--------|------------------|------------------------|--|--|-----------------------|--|-------|------------------|------------------------|--|--|
| CODE NO               | ITEM  | UNIT   | TOTAL QUANTITIES | X081-2A                |  |  | CODE NO               | ITEM   | UNIT  | TOTAL QUANTITIES | X081-2A                |  |  |
| 20200100              | EARTH EXCAVATION  | CU YD  | 36               | 36                     |  |  | * 78008210            | POLYUREA PAVEMENT MARKING TYPE I - LINE 4"                           | FOOT  | 232              | 232                    |  |  |
| 28100109              | STONE RIPRAP, CLASS A5  | SQ YD  | 569              | 569                    |  |  | * 78100105            | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)                           | EACH  | 1                | 1                      |  |  |
| 28200200              | FILTER FABRIC   | SQ YD  | 569              | 569                    |  |  | * 78100300            | REPLACEMENT REFLECTOR  | EACH  | 8                | 8                      |  |  |
| 35600712              | HOT-MIX ASPHALT BASE COURSE WIDENING, 9"                      | SQ YD  | 294              | 294                    |  |  | * 78200520            | BARRIER WALL MARKERS, TYPE B   | EACH  | 6                | 6                      |  |  |
| 40200900              | AGGREGATE SURFACE COURSE, TYPE B                              | CU YD  | 8                | 8                      |  |  | * 78200530            | BARRIER WALL MARKERS, TYPE C   | EACH  | 6                | 6                      |  |  |
| 44004250              | PAVED SHOULDER REMOVAL  | SQ YD  | 293              | 293                    |  |  | 78300100              | PAVEMENT MARKING REMOVAL   | SQ FT | 468              | 468                    |  |  |
| 48102100              | AGGREGATE WEDGE SHOULDER, TYPE B                              | TON    | 8                | 8                      |  |  | 78300200              | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                            | EACH  | 9                | 9                      |  |  |
| 50101700              | REMOVAL OF EXISTING SUPERSTRUCTURES NO.1                      | EACH   | 1                | 1                      |  |  | X0325305              | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 135              | 135                    |  |  |
| 50102400              | CONCRETE REMOVAL  | CU YD  | 2.8              | 2.8                    |  |  | X7200200              | WIDE LOAD SIGNING  | L SUM | 1                | 1                      |  |  |
| 50300100              | FLOOR DRAINS  | EACH   | 6                | 6                      |  |  | Z0030250              | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3        | EACH  | 2                | 2                      |  |  |
| 50300255              | CONCRETE SUPERSTRUCTURE                                       | CU YD  | 11.3             | 11.3                   |  |  | Z0030350              | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3         | EACH  | 2                | 2                      |  |  |
| 50300260              | BRIDGE DECK GROOVING  | SQ YD  | 173              | 173                    |  |  |                       |  |       |                  |                        |  |  |
| 50300300              | PROTECTIVE COAT   | SQ YD  | 229              | 229                    |  |  |                       |  |       |                  |                        |  |  |
| 50301200              | CONCRETE WEARING SURFACE                                      | SQ YD  | 184              | 184                    |  |  |                       |  |       |                  |                        |  |  |
| 50400505              | PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)           | SQ FT  | 1725             | 1725                   |  |  |                       |  |       |                  |                        |  |  |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED                              | POUND  | 5000             | 5000                   |  |  |                       |  |       |                  |                        |  |  |
| 50800515              | BAR SPLICERS  | EACH   | 54               | 54                     |  |  |                       |  |       |                  |                        |  |  |
| 51500100              | NAME PLATES   | EACH   | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 52000110              | PREFORMED JOINT STRIP SEAL                                    | FOOT   | 35               | 35                     |  |  |                       |  |       |                  |                        |  |  |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                               | CAL MO | 4                | 4                      |  |  |                       |  |       |                  |                        |  |  |
| 67100100              | MOBILIZATION  | L SUM  | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 70100500              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326               | L SUM  | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 70101205              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)     | EACH   | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 70106600              | TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER) | EACH   | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 70106700              | TEMPORARY RUMBLE STRIP  | EACH   | 6                | 6                      |  |  |                       |  |       |                  |                        |  |  |
| 70106800              | CHANGEABLE MESSAGE SIGN                                       | CAL MO | 1                | 1                      |  |  |                       |  |       |                  |                        |  |  |
| 70300220              | TEMPORARY PAVEMENT MARKING - LINE 4"                          | FOOT   | 1547             | 1547                   |  |  |                       |  |       |                  |                        |  |  |
| 70300240              | TEMPORARY PAVEMENT MARKING - LINE 6"                          | FOOT   | 550              | 550                    |  |  |                       |  |       |                  |                        |  |  |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                            | SQ FT  | 516              | 516                    |  |  |                       |  |       |                  |                        |  |  |
| 70400100              | TEMPORARY CONCRETE BARRIER                                    | FOOT   | 300              | 300                    |  |  |                       |  |       |                  |                        |  |  |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                           | FOOT   | 250              | 250                    |  |  |                       |  |       |                  |                        |  |  |
| * 78000200            | THERMOPLASTIC PAVEMENT MARKING - LINE 4"                      | FOOT   | 1315             | 1315                   |  |  |                       |  |       |                  |                        |  |  |

\*SPECIALTY ITEMS

|   |                           |            |           |   |                              |                           |         |                     |              |              |  |
|---|---------------------------|------------|-----------|---|------------------------------|---------------------------|---------|---------------------|--------------|--------------|--|
| FILE NAME =   | USER NAME = muenstermannk | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> | F.A.P. RTE.               | SECTION | COUNTY              | TOTAL SHEETS | SHEET NO.    |  |
| ct\projects\ed89507\plan\pin89507a.dgn                |                           | DRAWN -    | REVISED - |   |                              | 310                       | 57BR-1  | JERSEY              | 25           | 3            |  |
|   |                           | CHECKED -  | REVISED - |   |                              | CONTRACT NO. 76B20        |         |                     |              |              |  |
|   |                           | DATE -     | REVISED - |   |                              | ILLINOIS FED. AID PROJECT |         |                     |              |              |  |
| PLOT SCALE = 18.8889' / IN.<br>PLOT DATE = 12/19/2007 |                           |            |           |   |                              | SCALE:                    |         | SHEET NO. OF SHEETS |              | STA. TO STA. |  |

Rev: