

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000	-----	-----	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I-000	-----	-----
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1348	1348			54248515	CONCRETE COLLAR	EACH	2	2		
25000210	SEEDING, CLASS 2A	ACRE	0.9	0.9			542A2755	PIPE CULVERTS, CLASS A, TYPE 4 30"	FOOT	23	23		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81			60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6	6		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81			60107700	PIPE UNDERDRAINS 6"	FOOT	3200	3200		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81			*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	423	423		
25100115	MULCH, METHOD 2	ACRE	0.9	0.9			*63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	8	8		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	90	90			*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
28000300	TEMPORARY DITCH CHECKS	EACH	4	4			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
28000400	PERIMETER EROSION BARRIER	FOOT	1053	1053			67100100	MOBILIZATION	L SUM	1	1		
28000500	INLET AND PIPE PROTECTION	EACH	4	4			70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	3378	3378			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
30201500	LIME	TON	33	33			70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	160	160			70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	889	889			70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	192	192			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21819	21819		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33.3	33.3			70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40600300	AGGREGATE (PRIME COAT)	TON	161	161			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	79898	79898		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	3407	3407			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	337	337		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	850	850			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8878	8878		
40600990	TEMPORARY RAMP	SQ YD	307	307			*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62.4	62.4		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	6813	6813			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81,802	81802		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.17	0.17			*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	337	337		
40800030	AGGREGATE (PRIME COAT)	TON	0.8	0.8			*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	729	729		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	45	45			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	402	402		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	104093	104093			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	20		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1493.3	1493.3			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	1050	1050			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	375	375		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3200	3200			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	400	400									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1180	1180									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1423	1423									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1747	1747									
50105220	PIPE CULVERT REMOVAL	FOOT	16	16									
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2									

*SPECIALTY ITEMS Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	SECTION 805 (101,102,61-1-10RS)	COUNTY MARION	TOTAL SHEETS 81	SHEET NO. 3	
#FILE#		DRAWN - ---	REVISED - ---			CONTRACT NO. 76833							
		CHECKED - ---	REVISED - ---			ILLINOIS FED. AID PROJECT							
		DATE - ---	REVISED - ---										