PAVEMENT MARKING SCHEDULE

LOCATION			THERMOPLASTIC PAVEMENT MARKING					PAVEMENT MARKING REMOVAL (SQ. FT.)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ. FT.)	TEMPORARY PAVEMENT MARKING			SHORT-TERM PAVEMENT MARKING (FT.)
			SOLID YELLOW - 4"	SKIP-DASH YELLOW - 4"	CROSSWALK WHITE - 8"	DIAGONAL WHITE - 12"	STOP BAR WHITE - 12"			YELLOW LINE - 4" (FT.)	WHITE LINE - 8" (FT.)	WHITE LINE - 12" (FT.)	
STATION	TO	STATION	(FT.)	(FT.)	(FT.)	(FT.)	(FT.)						
366+23	TO	386+41	2018					13.3	67	2018			605
366+23	TO	386+41		510				169.8		510			
379+15							12	1.0	12			12	108
379+40					24	18		1.3	34		24	18	306
400+14							22	17.0	7			22	66
400+14	TO	400+22						10.7					
TOTALS			2528		24	52		213	121	2528	24	52	1085

QUANTITY HAS BEEN INCLUDED TO REMOVE AND REPLACE THE RIGHT SIDE OF THE BIDIRECTIONAL TURN LANE PAVEMENT MARKING.

RESURFACING SCHEDULE

LOCATION		HMA SURFACE REMOVAL 2" (SQ YD)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	HMA SURFACE COURSE 2" (TON)
START STATION	END STATION				
SOUTHBOUND					
366+23	386+21	2442	3.82	3.66	273.5
TOTALS		2442	3.8	3.7	274

TEMPORARY RAMP SCHEDULE

LOCATION		TEMPORARY RAMP (SQ YD)
START STATION	END STATION	
SOUTHBOUND		
366+43		4.4
370+39	370+59	14.8
373+88	374+08	14.8
377+37	377+57	14.8
380+87	381+07	14.8
384+38	384+58	14.8
	386+21	4.4
TOTALS		83

PCC BASE COURSE WIDENING & PAVEMENT REMOVAL

LOCATION		PCC BASE COURSE WIDENING (SQ YD)	PAVEMENT REMOVAL (SQ YD)
START STATION	END STATION		
SOUTHBOUND			
366+29	373+74	496.7	496.7
374+10	386+08	798.7	798.7
TOTALS		1295	1295

WIDENING SHALL BE TIED TO EXISTING CCC&G WITH NO. 6 TRANSVERSE TIE BARS, 24" LONG, EMBEDDED 8" AT 24" CENTERS ACCORDING TO ARTICLES 420.05(b) AND 508.07(b).

PATCHING SCHEDULE

PATCH NO.	STARTING STATION	ENDING STATION	LT OR RT	LENGTH (FT)	WIDTH (FT)	CL D TYPE I (SQ YD)	CLASS C TYPE III (SQ YD)	CLASS C TYPE IV (SQ YD)
SOUTHBOUND								
1	366+23	366+29	RT	6	6	4.0		
2	373+74	373+80	RT	6	6	4.0		
3	374+04	374+10	RT	6	6	4.0		
4	386+08	386+14	RT	6	6	4.0		
5	400+14	400+39	RT	25	6		16.7	
NORTHBOUND								
6	369+40	370+10	RT	70	6			46.7
10% ALLOWANCE FOR ANTICIPATED FAILURES						1.6	1.7	4.7
TOTALS						18	18	51

FILE NAME = c:\projects\ed02808\plan\plr02808e.dgn	USER NAME = alfordb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.6465 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/3/2007	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	271-3	ST CLAIR	13	4
		CONTRACT NO. 76856		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		