

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HSIP 90% FEDERAL / 10% STATE			
				LOCATION 1 IL 1 WHITE COUNTY	LOCATION 2 IL 149 FRANKLIN COUNTY	LOCATION 3 IL 166 WILLIAMSON COUNTY	LOCATION 4 US 45 MASSAC COUNTY
				SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A
	CONSTRUCTION TYPE CODE						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	39	0	0	39	0
20200100	EARTH EXCAVATION	CUYD	886	0	0	886	0
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	342	67	120	76	79
25000350	SEEDING, CLASS 7	ACRE	0.46	0	0	0.46	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	74	0	0	74	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	56	0	0	56	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	56	0	0	56	0
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.92	0	0	0.92	0
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	0.46	0	0	0.46	0
25100115	MULCH, METHOD 2	ACRE	0.92	0	0	0.92	0
25100630	EROSION CONTROL BLANKET	SOYD	112	0	0	112	0
28000300	TEMPORARY DITCH CHECKS	EACH	4	0	0	4	0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SOYD	8,057	1,428	2,595	2,315	1,719
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	6,030.0	1,437.5	1,292.5	3,075.0	225.0
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURE	FOOT	37.5	25	12.5	0	0
63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	5	2	1	0	2
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	0	4	4	0
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL)-TANGENT	EACH	30	12	3	12	3
63200310	GUARDRAIL REMOVAL	FOOT	2,736	479	998	1,159	100
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	52	26	13	0	13
67100100	MOBILIZATION	L SUM	1.0	0.25	0.25	0.25	0.25
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	0.25	0.25	0.25	0.25
78200405	GUARDRAIL MARKER	EACH	180	53	34	76	17
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	35	14	4	12	5

• FAP 782, FAP 873, FAS 904, FAS 961  
 \*\* WHITE, FRANKLIN, WILLIAMSON, MASSAC