

LOCATION #3 HOT-MIX ASPHALT SHOULDER SCHEDULE

LOCATION STATION TO STATION	GROSS LENGTH	NET LENGTH	HOT MIX ASPHALT SHOULDERS, 6"	EXCAVATING AND GRADING EXISTING SHOULDERS	REMARKS
	FOOT	FOOT	SQYD	UNIT	
IL 166 WILLIAMSON COUNTY					
LT 148+67 TO LT 171+30	2,163	2,021	450.0	21.0	2' WIDE SHOULDER
RT 148+60 TO RT 171+30	2,270	2,180	485.0	22.0	2' WIDE SHOULDER
LT 171+30 TO LT 177+27	597	597	266.0	6.0	4' WIDE SHOULDER
RT 171+30 TO RT 177+55	625	625	278.0	7.0	4' WIDE SHOULDER
LT 178+80 TO LT 188+25	945	945	420.0	10.0	4' WIDE SHOULDER
RT 178+91 TO RT 188+25	934	934	416.0	10.0	4' WIDE SHOULDER
LOCATION #3 TOTAL			2,315	76	

IL 166 OMISSIONS

STATION	TYPE	WIDTH
		FOOT
RT 154+78	PRIVATE ENTRANCE	26
RT 156+52	PRIVATE ENTRANCE	35
LT 159+37	PRIVATE ENTRANCE	39
LT 161+14	PRIVATE ENTRANCE	47
LT 162+89	PRIVATE ENTRANCE	27
RT 167+05	PRIVATE ENTRANCE	38
LT 170+47	PRIVATE ENTRANCE	29

LOCATION #3 - IL 166 SHOULDER SCHEDULE

LOCATION #4 HOT-MIX ASPHALT SHOULDER SCHEDULE

LOCATION STATION TO STATION	GROSS LENGTH	NET LENGTH	HOT MIX ASPHALT SHOULDERS, 6"	EXCAVATING AND GRADING EXISTING SHOULDERS	REMARKS
	FOOT	FOOT	SQYD	UNIT	
US 45 MASSAC COUNTY					
LT 111+60 TO LT 118+55	695	695	155.0	7.0	2' WIDE SHOULDER
RT 111+60 TO RT 118+05	645	645	144.0	7.0	2' WIDE SHOULDER
LT 123+63 TO LT 158+00	3,437	3,213	714.0	33.0	2' WIDE SHOULDER
RT 123+00 TO RT 158+00	3,500	3,176	706.0	32.0	2' WIDE SHOULDER
LOCATION #4 TOTAL			1,719	79	

US 45 OMISSIONS

STATION	TYPE	WIDTH
		FOOT
RT 138+79	PRIVATE ENTRANCE	38
RT 142+57	PRIVATE ENTRANCE	37
LT 142+57	PRIVATE ENTRANCE	37
LT 143+64	PRIVATE ENTRANCE	39
RT 145+36	PRIVATE ENTRANCE	33
RT 146+52	PRIVATE ENTRANCE	40
LT 146+72	PRIVATE ENTRANCE	55
RT 147+71	PRIVATE ENTRANCE	30
LT 149+87	PRIVATE ENTRANCE	28
RT 150+20	HILLBROOK ROAD	41
RT 152+64	PRIVATE ENTRANCE	40
LT 153+75	PRIVATE ENTRANCE	65
RT 155+52	PRIVATE ENTRANCE	36
RT 156+61	PRIVATE ENTRANCE	29

LOCATION #4 - US 45 SHOULDER SCHEDULE

* FAP 782, FAP 873, FAS 904, FAS 961
 ** WHITE, FRANKLIN, WILLIAMSON, MASSAC

FILE NAME = c:\proj\jeeta\d90307\d90307p1.m32	USER NAME = russellcf	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHOULDER SCHEDULE				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.00' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	D-9 SAFETY FY08-3	16	9
	PLOT DATE = 11/21/2007	DATE -	REVISED -						CONTRACT NO. 78042		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		