

SUMMARY OF QUANTITIES

Code No.	Item	Unit	Total Quantity	SFTY-1B	SFTY-1D	SFTY-1E
20200100	EARTH EXCAVATION	Cu Yd	100	100		
21101615	TOPSOIL, FURNISH AND PLACE, 4"	Sq Yd	650	650		
25000310	SEEDING, CLASS 4	Acre	0.2	0.2		
25100105	MULCH METHOD 1	Acre	0.2	0.2		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	Sq Ft	200	200		
44000600	SIDEWALK REMOVAL	Sq Ft	200	200		
66400405	CHAIN LINK FENCE, 7'	Lin Ft	700	700		
66408300	CHAIN LINK GATE, 7'X8' DOUBLE	Each	2	2		
66410300	CHAIN LINK FENCE REMOVAL	Lin Ft	350	350		
67100100	MOBILIZATION	LSum	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	LSum	1	1		
72000100	SIGN PANEL, TYPE I	Sq Ft	18	18		
78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	Sq Ft	32		32	
78000200	THERMOPLASTIC PAVEMENT MARKING LINE, 4	Lin Ft	200		200	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	LSum	1			1
81000600	CONDUIT IN TRENCH, 2" DIAMETER GALV STEEL	Lin Ft	10			10
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIAMETER GALVANIZED STEEL	Lin Ft	510			510
81300210	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6X4X4	Each	6			6
81400100	HANDHOLE	Each	2			2
81603050	UNIT DUCT, 600V, 3 1/C No.6 & 1/C No.8 GROUND, (XLP-TYPE USE) 1" DIAMETER, POLYETHYLENE	Lin Ft	100			100
81702415	ELECTRICAL CABLE IN CONDUIT, 600 V, (XLP TYPE USE), 3 1/C No. 6, No. 8 Ground	Lin Ft	500			500
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	Lin Ft	700			700
82107505	UNDERPASS LUMINAIRE, 250 WATT, HIGH PRESSURE SODIUM, ALUMINUM HOUSING	Each	10			10
X0350800	BOLLARDS	Each	4	4		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSum	1	1		

Drawing file: W:\Projects\08003985 - Prairie Path Impr.\Index.dwg Jan 08, 2008 - 9:41am