

**SUMMARY OF QUANTITIES**

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1000-ZA PARTICIPATING	Y060 NON-PARTICIPATING
● 20800250	TRENCH BACKFILL, SPECIAL	CU YD	5,204	0	5,204
● 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	300	0	300
25000210	SEEDING, CLASS 2A	ACRE	0.063	0	0.063
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	0	6
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	0	6
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	0	6
25100401	EXCELSIOR BLANKET, SPECIAL	SQ YD	301	0	301
25200200	SUPPLEMENTAL WATERING	UNIT	6	0	6
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	18	18	0
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	18	18	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,893	3,893	0
40600300	AGGREGATE (PRIME COAT)	TON	78	78	0
40600990	TEMPORARY RAMP	SQ YD	1,369	1,369	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N70	TON	2,798	2,798	0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL 3 1/4"	SQ YD	19,461	19,461	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	18	18	0
44001900	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	1,964	1,964	0
44002000	CONCRETE CURB REMOVAL	FOOT	32	32	0
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	400	400	0
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	3,453	600	2,853
● 56103300	DUCTILE IRON WATER MAIN 12"	FOOT	2,345	0	2,345
● <del>XX007253</del>	DUCTILE IRON WATER MAIN 14"	FOOT	25	0	25
● 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	8	0	8
60260505	INLETS TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	2	2	0
60261320	INLETS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	1	1	0
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	0
60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	3	3	0
60600105	CONCRETE CURB	FOOT	32	32	0
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	1,328	1,328	0
60604800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (SPECIAL)	FOOT	636	636	0
67100100	MOBILIZATION	LSUM	1	0.73	0.27
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1	0.41	0.59
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	LSUM	1	0	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	38,700	2,700	36,000
● 70300600	TEMPORARY PAVEMENT MARKING, PAINT	FOOT	5,400	5,400	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12,900	900	12,000
● 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	377.2	377.2	0
● 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,738	7,738	0
● 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	610	610	0
● 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	420	420	0
● 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	219	219	0
● 88600600	DETECTOR LOOP REPLACEMENT	FOOT	521	521	0
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	13	13	0

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1000-ZA PARTICIPATING	Y060 NON-PARTICIPATING
Z0017500	DRAINAGE & UTILITY STRUCTURE ADJUSTMENT (SPECIAL)	EACH	20	20	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1	1	0
△ Z0076600	TRAINEES	HOUR	500	500	0
● XX001047	VALVE VAULTS TO BE ABANDONED	EACH	11	0	11
● XX002161	ABANDON EXISTING WATER MAIN	EACH	8	0	8
● XX003008	TRAFFIC CONTROL DETOUR	LSUM	1	0	1
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	46	46	0
● XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	4	0	4
● XX003517	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 6"	EACH	1	0	1
● XX003519	DUCTILE IRON WATER MAIN FITTING - 12" X 6" TEE	EACH	9	0	9
● XX003531	WATER SERVICE CONNECTION 1"	EACH	1	0	1
● XX003542	DUCTILE IRON WATER MAIN FITTINGS 6" 45 DEGREE BEND	EACH	2	0	2
● XX003543	DUCTILE IRON WATER MAIN FITTINGS 8" 45 DEGREE BEND	EACH	8	0	8
● XX003668	PRECONSTRUCTION VIDEO TAPING	LSUM	1	0	1
● <del>XX005221</del>	TOPSOIL FURNISH AND PLACE (PULVERIZED), VARIABLE DEPTH	SQ YD	301	0	301
● XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	4	0	4
● XX005107	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 12"	EACH	1	0	1
● XX005476	DUCTILE IRON WATER MAIN 12" RESTRAINED JOINT TYPE	FOOT	329	0	329
● XX005478	DUCTILE IRON WATER MAIN 6" RESTRAINED JOINT TYPE	FOOT	178	0	178
● XX005479	DUCTILE IRON WATER MAIN 8" RESTRAINED JOINT TYPE	FOOT	107	0	107
● XX005776	DUCTILE IRON WATER MAIN FITTINGS 45 BEND 12"	EACH	10	0	10
XX005924	TEMPORARY RAMP REMOVAL	SQ YD	1,369	1,369	0
● XX006113	REMOVE EXISTING FIRE HYDRANTS	EACH	8	0	8
● X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	128.5	51.4	77.1
● X0323189	DUCTILE IRON WATER MAIN TEE, 12" X 8"	EACH	4	0	4
● X0323190	DUCTILE IRON WATER MAIN TEE, 12" X 12"	EACH	2	0	2
● <del>XX007254</del>	DUCTILE IRON WATER MAIN REDUCER, 14" X 12"	EACH	2	0	2
X0712400	TEMPORARY PAVEMENT	SQ YD	2,853	0	2,853
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6	0
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,120	1,120	0
● <del>XX007219</del>	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 GRATE, OPEN LID	EACH	1	1	0
● X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	10	10	0
● <del>XX007220</del>	PVC CASING PIPE - 20"	FOOT	211	0	211
● <del>XX007221</del>	DUCTILE IRON WATER MAIN TEE, 14" X 12"	EACH	1	0	1
● <del>XX007222</del>	DUCTILE IRON WATER MAIN 14" CUTTING IN SLEEVE	EACH	1	0	1
● <del>XX007223</del>	GATE VALVE 14" WITH VAULT, 6' DIAMETER (VALVE ATTACHED TO LINE TEE)	EACH	1	0	1
● <del>XX007224</del>	GATE VALVE 12" WITH VAULT, 6' DIAMETER (VALVE ATTACHED TO LINE TEE)	EACH	1	0	1
● <del>XX007225</del>	GATE VALVE 8" WITH VAULT, 6' DIAMETER (VALVE ATTACHED TO LINE TEE)	EACH	4	0	4
● <del>XX007226</del>	GATE VALVE 6" WITH VAULT, 6' DIAMETER (VALVE ATTACHED TO LINE TEE)	EACH	1	0	1
● <del>XX007227</del>	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 14"	EACH	3	0	3

● INDICATES SPECIALTY ITEM  
△ Y080

I:\ADMIN\060486 - Grace STP (LAPP)\DWGS\060486-SQ.dwg - SH4  
 Plotter: 12-14-07 @ 11:20am By: 560kar  
 Copyright © 2006 by Baxter & Woodman, Inc.  
 State of Illinois Professional Design Expires 4-30-07  
 License No. - 184-00121



REVISIONS	
NAME	DATE
DOT REVIEW	11-16-07

VILLAGE OF ADDISON, ILLINOIS  
**FAU ROUTE 2619 SOUTH GRACE STREET**  
**SUMMARY OF QUANTITIES**  
 PROJECT NO. 060486.40 DESIGNED BY: MWP  
 SCALE: NONE DRAWN BY: UKB  
 DATE: 7-27-07 CHECKED BY: MWP