

SUMMARY OF QUANTITIES
CONSTRUCTION TYPE CODE: Y003

CODE NO.	ITEM	UNIT	TOTAL
* B2005716	T-PYRUS C CH TF 2	EACH	15
* C2C09918	SHRUBS - SPIREAXBUM GF 18C	EACH	8
* K0030450	PERENNIAL PL DAF BULB	UNIT	2.70
* K1005481	SHRED BARK MULCH 3	SQ. YD.	53
LR420021	PCC PAVEMENT, 6" SPL	SQ. YD.	50
LR430050	CONCRETE PAVER SIDEWALK	SQ. YD.	71
* XX002281	HEMEROCALLIS DAYLILY	UNIT	1.15
* XX005022	LANDSCAPE PLANTERS	L.S.	1
* XX006599	T-ACERX FREM ARM 3	EACH	9
20200100	EARTH EXCAVATION	CU. YD.	268
20400800	FURNISHED EXCAVATION	CU. YD.	100
* 21101615	TOPSOIL F& P 4	SQ. YD.	456
* 25000100	SEEDING, CLASS 1	ACRE	0.09
* 25100110	MULCH, METHOD 1	TON	0.18
35101400	AGGREGATE BASE COURSE, TYPE B	TON	599
42300300	PCC DRIVEWAY PAVT, 7"	SQ. YD.	318
42400200	PCC SIDEWALK 5"	SQ. FT.	9,762
42400800	DETECTABLE WARNINGS	SQ. FT.	128
44000100	PAVEMENT REM	SQ. YD.	970
44000200	DRIVEWAY PAVEMENT REM	SQ. YD.	318
44000300	CURB REM	FT.	417
44000600	SIDEWALK REM	SQ. FT.	12,112
40800050	INC HMA SURF	TON	304
60264000	INL RECON NEW T 12 F&G	EACH	3
60605000	COMB C C&G T B6.24	FT.	1,121
67100100	MOBILIZATION	L.S.	1
70101700	TRAFFIC CONTROL AND PROTECTION	L.S.	1

* SPECIALTY ITEMS

GENERAL NOTES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGE TO EXISTING INSTALLATIONS CAUSED BY THE EXECUTION OF THE WORK.

ALL EXCAVATION FOR STRUCTURES SHALL BE KEPT DEWATERED DURING CONSTRUCTION OPERATIONS UNTIL BACKFILL IS IN PLACE.

ALL EXCESS EARTH EXCAVATION TO BE DISPOSED OF BY CONTRACTORS.

ALL PROPERTY SHALL BE RESTORED TO THE CONDITION EXISTING BEFORE CONSTRUCTION BEGAN.

NOTES

- CONTRACTOR SHALL VISIT SITE, INSPECT EXISTING CONDITIONS AND REVIEW PROPOSED PLANTING AND RELATED WORK.
- CONTRACTOR SHALL VERIFY LOCATIONS OF ALL ON-SITE UTILITIES PRIOR TO BEGINNING CONSTRUCTION ON HIS PHASE OF WORK. ELECTRIC, GAS, TELEPHONE, AND CABLE TELEVISION MAY BE LOCATED BY CALLING J.U.L.I.E. AT (1-800-892-0123). ANY DAMAGE OR INTERRUPTION OF SERVICES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR TO COORDINATE ALL RELATED ACTIVITIES WITH OTHER TRADES ON THE JOB AND SHALL REPORT ANY UNACCEPTABLE JOB CONDITIONS TO OWNER'S REPRESENTATIVE PRIOR TO COMMENCING WORK.
- CONTRACTOR RESPONSIBLE FOR APPLICATION AND COST OF ALL NECESSARY BUILDING PERMITS AND CODE VERIFICATIONS. SUBMIT COPIES OF ALL DOCUMENTS TO OWNER AND ENGINEER.
- ACCEPTANCE OF GRADING AND SEEDING SHALL BE BY ENGINEER AND OWNER. THE CONTRACTOR SHALL ASSUME MAINTENANCE RESPONSIBILITIES FOR A MINIMUM OF SIXTY (60) DAYS OR UNTIL SECOND CUTTING, WHICHEVER IS LONGER. MAINTENANCE SHALL INCLUDE WATERING, WEEDING, RESEEDING, AND OTHER OPERATIONS NECESSARY TO KEEP LAWN IN A THRIVING CONDITION. UPON FINAL ACCEPTANCE BY ENGINEER AND/OR OWNER, OWNER SHALL ASSUME ALL MAINTENANCE RESPONSIBILITIES. AFTER LAWN AREAS HAVE GERMINATED, AREAS WHICH FAIL TO SHOW A UNIFORM STAND OF GRASS FOR ANY REASON WHATSOEVER SHALL BE RESEEDED REPEATEDLY UNTIL ALL AREAS ARE COVERED WITH A SATISFACTORY STAND OF GRASS. MINIMUM ACCEPTANCE OF SEEDED LAWN AREAS MAY INCLUDE SCATTERED BARE SPOTS, NONE OF WHICH ARE LARGER THAN ONE SQUARE FOOT AND WHEN COMBINED DO NOT EXCEED 2% OF TOTAL SEEDED AREA.
- CONCRETE UNIT PAVERS SHALL BE "HOLLANDSTONE" BY UNILOCK OR "HOLLAND STONE" BY BELGARD LANDSCAPES. COLOR SHALL BE DETERMINED BY ENGINEER AND/OR OWNER PRIOR TO ORDER DATE.
4" w x 8" l x 2 3/8" h