

SUMMARY OF QUANTITIES

QTY.	UNIT	ITEM	CODE
306	FOOT	ELECTRIC CABLE IN CONDUIT, NO. 10, 2C	XX007261 *
4	EACH	LIGHT POLE, SPECIAL	XX001136 *
32	CU YD	EARTH EXCAVATION	20200100
54	CU YD	CHANNEL EXCAVATION	20300100
265	CU YD	FURNISHED EXCAVATION	20400800
0.50	ACRE	SEEDING, CLASS 1 (SPECIAL)	25000900
71	TON	STONE DUMPED RIPRAP, CLASS A4	28100807
1946	SQ YD	PROCESSING MODIFIED SOIL 12"	30200650
49	TON	LIME	30201500
50	TON	AGGREGATE SURFACE COURSE, TYPE B	40200800
1636	SQ YD	PORTLAND CEMENT CONCRETE PAVEMENT 8"	42000300
1636	SQ YD	PAVEMENT FABRIC	42001200
94	SQ YD	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	42300200
2507	SQ FT	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	42400100
1706	SQ FT	PORTLAND CEMENT CONCRETE SIDEWALK SPECIAL	42400500
50	SQ FT	DETECTABLE WARNINGS	42400800
878	SQ YD	PAVEMENT REMOVAL	44000100
81	SQ YD	DRIVEWAY PAVEMENT REMOVAL	44000200
533	FOOT	COMBINATION CURB AND GUTTER REMOVAL	44000500
441	SQ FT	SIDEWALK REMOVAL	44000600
1200	SQ YD	PAVEMENT REMOVAL (SPECIAL)	44004400
1	EACH	REMOVAL OF EXISTING STRUCTURES	50100100
3	EACH	FLOOR DRAINS	50300100
89900	POUND	REINFORCEMENT BARS, EPOXY COATED	50800205
198	FOOT	ALUMINUM RAILING	50900500
1	EACH	NAME PLATES	51500100
414.4	CU YD	CONCRETE BOX CULVERTS	54003000
208	FT	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	55019500
104	FT	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	55019600
206	FT	STORM SEWER REMOVAL 12"	55100500
18	FT	STORM SEWER REMOVAL 15"	55100700
743.4	CU YD	CONTROLLED LOW-STRENGTH MATERIAL	59300100
20	FOOT	PIPE DRAINS 4"	60100905
2	EACH	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	60235300
7	EACH	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	60236800
2	EACH	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	60240215
2	EACH	MANHOLES TO BE ADJUSTED	60255500
8	EACH	REMOVING INLETS	60500060
926	FOOT	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	60605000
50	FOOT	STEEL PLATE BEAM GUARD RAIL, TYPE B	63000005 *
237	FOOT	STEEL PLATE BEAM GUARD RAIL REMOVAL	63200305
6	CAL MO	ENGINEERS FIELD OFFICE, TYPE B	67000500
1	L SUM	MOBILIZATION	67100100
1	L SUM	TRAFFIC CONTROL AND PROTECTION	70101700
1	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	70102440
6	SQ FT	SIGN PANEL - TYPE 1	72000100
26	FOOT	METAL POST - TYPE B	72900200
24	SQ FT	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	78003100 *
110	FOOT	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	78003110 *
374	FOOT	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	78003150 *
39	FOOT	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	78003180 *
1	L SUM	ELECTRIC UTILITY SERVICE CONNECTION	80400200 *
174	FOOT	CONDUIT IN TRENCH, 3/4" DIA., PVC	81012200 *
132	FOOT	CONDUIT EMBEDDED IN STRUCTURE, 3/4" DIA., PVC	81200200 *
174	FOOT	TRENCH AND BACKFILL FOR ELECTRIC WORK	81900200 *
4	EACH	LIGHT POLE FOUNDATION	83600100 *

* SPECIALTY ITEMS

