



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 3, 2008

SUBJECT: Project SBIL-TE-00D8(113)
Section 03-00026-00-PK & 06-00026-01-MS (Hartford)
Madison County
Contract No. 97331
Item 145
March 7, 2008 Letting
Addendum (B)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Plans – Sheet 3, 6, 8, 21, 23, 25, & 42.

Proposal – Page 10 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." monogram.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

LEWIS & CLARK MEMORIAL TOWER

**LEWIS & CLARK RESTROOMS
SECTION 03-00026-00-PK
LEWIS & CLARK WELCOME CENTER
SECTION 06-00026-01-MS
VILLAGE OF HARTFORD**

10-02048

This work is subject to inspection by the Wood River Drainage and Levee District and the U.S. Army Corps of Engineers who may impose additional restrictions on this work. Additional requirements imposed by either of the above agencies will be paid for in accordance with Article 109.04 of the Standard Specifications.

MANHOLES (LEAKAGE TESTING)

Prior to placing the completed sanitary system in service, each manhole shall be tested for leakage in accordance with ASTM C1244-02. Failing manholes shall be repaired and retested as necessary to achieve an acceptable result.

This work will be measured complete in place and paid for at the contract unit price per each for MANHOLES (LEAKAGE TESTING).

MANHOLES, TYPE A, 4' DIAMETER, WATERPROOF FRAME & BOLTED LID

This item of work consists of furnishing and installing sanitary manholes at the locations shown on the plans or as directed by the Engineer. The sanitary manholes shall be constructed in accordance with the requirements set forth in SECTION 602. CATCH BASIN, MANHOLE, INLET, DRAINAGE STRUCTURE, AND VALVE VAULT CONSTRUCTION, ADJUSTMENT, AND RECONSTRUCTION of the Standard Specifications, except that the frame and lid shall be as shown in the Construction Plans.

This work will be paid for at the contract unit price per each for MANHOLES, TYPE A, 4' DIAMETER, WATERPROOF FRAME & BOLTED LID.

OUTFALL STRUCTURE

This item of work consists of the construction of an outfall structure at the location shown on the plans. The outfall structure shall be constructed in accordance with the details shown on the Construction Plans, the applicable requirements of the American Concrete Institute, and generally in accordance with the applicable requirements of Section 503. Concrete Structures of the Standard Specifications. The work shall include all ancillary items shown on the construction plans and the finished product shall function as indicated. Precasting of the structure will be allowed.

The Contractor shall furnish seven (7) detailed sets of shop drawings, and/or specifications showing the type and pertinent information of the proposed outfall structure and the method of construction, to the Engineer for approval before beginning fabrication and/or construction. The Engineer shall review this submittal and return same to the Contractor within fifteen (15) days, following receipt, stating approval thereof or required revisions and resubmittal. Resubmittals shall adhere to the same time constraint. Three (3) sets of approved shop drawings will be returned to the Contractor before any work shall be commenced on this item.