

PARTIAL ROOF PLAN

NOTES:

NOTES:

1. ROOF CONSTR: RIGID INSULATION ON 4'-0"X8" DP. (MAX.) PRESTRESSED HOLLOW CORE NORM. WT. CONC. SLAB. (TYPE 4HC8-66-S OR APPROVAL EQUAL), TOP OF SLAB VARIES DESIGN CRITERIA: DL = 20PSF

2. ALL EMBEDS ARE GALVANIZED WHERE EXPOSED.

3. PRECAST CONTRACTOR TO PROVIDE CONNECTION BETWEEN WALL PANEL TO WALL PANEL, WALL PANEL TO COL. FOR 200 Ibs/ft in BOTH DIRECTIONS.

4. PRECASTER IS RESPONSIBLE FOR COORDINATING FABRICATION OF CONCRETE PANELS WITH LOCATION OF ALL ELECTRICAL, AND PLUMBING DEVICES. PANELS SHOULD BE DESIGNED TO INCLUDE ALL KNOCKOUTS AND VOIDS REQUIRED FOR DUCTWORK AND JUNCTION BOXES. THEY SHOULD ALSO INCLUDE CONDUIT FOR THE WIRING OF ALL DEVICES.

Sheetille 97331

211 N. Broadway
Suite 1900
St. Louis, MO
63102
(314) 241-8188
X (314) 241-0125

TOWER

ILLINOIS CLARK MEMORIAL

WILLAGE OF HARTFORD, Hartford, Illinois 62049 AND Lewis

PLAN ROOF PARTIAL

DATE						
REMARKS						

KENNEDY PROJECT NO KAI# 10-02048

ISSUE DATE 20-DEC-07 The seal(s) and signature(s) apply only to the document to which they are affixed, on expressly disclaim any responsibility for all other plans, specifications, estimates, report or other documents or instruments relating to or intended to be used for any part or parts of the architectural or engineering project.

SHEET NO

S2.3

SSE PROJECT NO: 02111