

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	RURAL - WILLIAMSON COUNTY HBP FUNDING		
			TOTAL QUANTITY	80% FEDERAL; CONSTRUCTION TYPE CODE X171-2A SN 100-0090	20% STATE CONSTRUCTION TYPE CODE X071-2A SN 100-0091
				QUANTITY	QUANTITY
				QUANTITY	QUANTITY
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	202	79	123
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4''	FOOT	313	153	160
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1125	875	250
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	6	4	2
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	1		1
63200310	GUARDRAIL REMOVAL	FOOT	946	642	304
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5
70101805	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2		2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6		6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	2	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	263	173	90
70300220	TEMPORARY PAVEMENT MARKING - LINE 4''	FOOT	7705	5650	2055
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2656	1941	715
70400100	TEMPORARY CONCRETE BARRIER	FOOT	475		475
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	212.5		212.5
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	650	650	
70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2		2
* 78001110	PAINT PAVEMENT MARKING - LINE 4''	FOOT	6963	4200	2763
* 78200405	GUARDRAIL MARKERS	EACH	49	33	16
* 78200500	BARRIER WALL MARKERS	EACH	20	12	8
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	13	8	5
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1760	1400	360
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	3	3

CODE NUMBER	ITEM DESCRIPTION	UNIT	RURAL - WILLIAMSON COUNTY HBP FUNDING		
			TOTAL QUANTITY	80% FEDERAL; CONSTRUCTION TYPE CODE X171-2A SN 100-0090	20% STATE CONSTRUCTION TYPE CODE X071-2A SN 100-0091
				QUANTITY	QUANTITY
				QUANTITY	QUANTITY
XX006661	UNINTERRUPTIBLE POWER SUPPLY	EACH	4	2	2
X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SQ YD	298	133	165
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	870		870
* X6330115	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, REMOVE AND RELOCATE	EACH	1		1
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	6	4	2
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
50157300	PROTECTIVE SHIELD	SQ YD	409	409	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
* Z0065000	SETTING PILES IN ROCK	EACH	16		16
70500670	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	

* SPECIALTY ITEMS