

INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3. SUMMARY OF QUANTITIES
- 4-10. BRIDGE REPAIR PLANS (SN 049-0033)
- 11-13. STAGING PLANS
14. TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
15. ARTERIAL ROAD INFORMATION SIGN (TC-22)
- 15A. TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
- 15B. DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)

STATE STANDARDS

STANDARD NO.	DESCRIPTION
420001-07	PAVEMENT JOINTS
442101-07	CLASS B PATCHES
701101-03	OFF ROAD OPERATIONS, MULTILANE, \leq 15 FT TO EOP
701421-05	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS \leq 45 MPH TO 55 MPH
701426-05	LANE CLOSURE, MULTIALNE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS \geq 45 MPH
701901-02	TRAFFIC CONTROL DEVICES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED).
- THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
- DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, AND THE CITY OF LAKE FOREST.
- THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE BRIDGE INSPECTORS.
- ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- FOR ACCESS INTO THE VAULTED AREAS THE CONTRACTOR SHALL CONTACT THE BUREAU OF MAINTENANCE AT (847) 705-4181 FOR WORK IN THE NORTH VAULTED ABUTMENT AND ELECTRICAL MAINTENANCE OPERATION AT (708) 524-2145 FOR WORK IN THE SOUTH VAULTED ABUTMENT.
- USE #8 EPOXY-COATED TIE BARS, CONFORMING TO ART. 1006.10 OF THE STANDARD SPECIFICATIONS, FOR ALL TIE BARS. USE THE "LONGITUDINAL CONSTRUCTION JOINT (TIE BAR GROUTED IN PLACE)" DETAIL SHOWN ON HIGHWAY STANDARD 420001 FOR ALL LONGITUDINAL JOINTS.
- CONCRETE SUPERSTRUCTURE SHALL HAVE A SEVEN DAY MINIMUM CURE.

FILE NAME =	USER NAME = pyzanoskiqb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\p1010\pyzanoskiqb\031068	0141412-shit-plan.dgn	DRAWN -	REVISED -			346	1305-11(2)	LAKE	15	2	
MODELNAME	PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -			CONTRACT NO. 60T65					
	PLOT DATE = 1/28/2013	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.