

| SUMMARY OF QUANTITIES |   |        |                  | URBAN<br>100%<br>STATE<br>TOTAL<br>QUANTITIES |  |  |  |  | CONSTRUCTION TYPE CODE 0014 |   |       |                  |        | SUMMARY OF QUANTITIES |  |  |  | CONSTRUCTION TYPE CODE |  |  |  |  |
|-----------------------|---|--------|------------------|---|--|--|--|--|-----------------------------|---|-------|------------------|--------|-----------------------|--|--|--|------------------------|--|--|--|--|
| CODE NO               | ITEM                                      | UNIT   | TOTAL QUANTITIES | 0014  |  |  |  |  | CODE NO                     | ITEM  | UNIT  | TOTAL QUANTITIES | 0014   |                       |  |  |  |                        |  |  |  |  |
| 44201019              | CLASS B PATCHES, TYPE II, 14 INCH         | SO YD  | 39               | 39  |  |  |  |  | *78008210                   | POLYUREA PAVEMENT MARKING<br>TYPE I 4 INCH        | FOOT  | 1135             | 1135   |                       |  |  |  |                        |  |  |  |  |
| 44213202              | TIE BARS 1"                               | EACH   | 25               | 25  |  |  |  |  | 78300100                    | PAVEMENT MARKING REMOVAL                          | SQ FT | 612              | 612    |                       |  |  |  |                        |  |  |  |  |
| 50102400              | CONCRETE REMOVAL                          | CU YD  | 12.1             | 12.1  |  |  |  |  | X5870015                    | BRIDGE DECK CONCRETE<br>SEALER                    | SQ FT | 45,030           | 45,030 |                       |  |  |  |                        |  |  |  |  |
| 50300255              | CONCRETE SUPERSTRUCTURE                   | CU YD  | 11.9             | 11.9  |  |  |  |  | X7030030                    | WET REFLECTIVE TEMPORARY<br>TAPE TYPE III, 4 INCH | FOOT  | 8180             | 8180   |                       |  |  |  |                        |  |  |  |  |
| 50800205              | REINFORCEMENT BARS, EPOXY COATED          | POUND  | 1454             | 1454  |  |  |  |  | Z0030850                    | TEMPORARY INFORMATION<br>SIGNING                  | SQ FT | 51.4             | 51.4   |                       |  |  |  |                        |  |  |  |  |
| 50800515              | BAR SPLICERS                              | EACH   | 32               | 32  |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| 52000110              | PREFORMED JOINT STRIP SEAL                | FOOT   | 276              | 276   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| 59300100              | CONTROLLED LOW-STRENGTH MATERIAL          | CU YD  | 233              | 233   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| 67000400              | ENGINEER'S FIELD OFFICE, TYPE A           | CAL MO | 3                | 3   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| 67100100              | MOBILIZATION                              | L SUM  | 1                | 1   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| X7010216              | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM  | 1                | 1   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| Z0016200              | DECK SLAB REPAIR (PARTIAL)                | SO YD  | 27               | 27  |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| 70301000              | WORK ZONE PAVEMENT MARKING<br>REMOVAL     | SQ FT  | 2727             | 2727  |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |
| *78000200             | THERMOPLASTIC PAVEMENT<br>MARKING LINE 4" | FOOT   | 700              | 700   |  |  |  |  |                             |   |       |                  |        |                       |  |  |  |                        |  |  |  |  |

\* Specialty Items

|             |             |            |           |   |                       |           |    |        |   |         |        |              |           |    |   |
|-------------|-------------|------------|-----------|---|-----------------------|-----------|----|--------|---|---------|--------|--------------|-----------|----|---|
| FILE NAME * | USER NAME * | DESIGNED - | REVISED - | STATE OF ILLINOIS<br>DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES |           |    |        | F.A.P. RTE.                                     | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |    |   |
|             |             | DRAWN -    | REVISED - |   | SCALE:                | SHEET NO. | OF | SHEETS | STA.  | TO STA. | 346    | 1305-1(12)   | LAKE      | 15 | 3 |
|             |             | CHECKED -  | REVISED - |   |                       |           |    |        | CONTRACT NO. 60T65                              |         |        |              |           |    |   |
|             |             | DATE       | REVISED - |   |                       |           |    |        | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT |         |        |              |           |    |   |