CIVIL ENGINEERING CONSULTANTS
RWA
8619 W. Bryn Mawr Ave., Suite 602
Chicago, IL 60631-3511
773-283-2600 Fax: 773-283-2602
www.RWAengineers.com
Regina Webster & Associates, Inc.

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																											
				1	2	3	4	5	6	7	8	9	10	11	13	14	15	16	17	19	20	21	22								
				TRAFFIC SIGNAL																											
				0021																											
				URBAN																											
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	12			1					1		1	4	4				1												
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	32				5	4			7					8					8										
88500100	INDUCTIVE LOOP DETECTOR	EACH	21								21																				
88800100	PEDESTRIAN PUSH-BUTTON	EACH	35			2	2		2		13	2	4	4							4	2									
89100400	ILLUMINATED SIGN, LED	EACH	8				4											4													
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	37	3	1	1	11	1	1	1	3	2	2	1	1	1	1	1	2	1	1	1	1								
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	20			2	2	1	1		4	1	2	2	1	1			1		1	1									
X0326310	RELOCATE EXISTING SWITCH (SPECIAL)	EACH	2								2																				
X0327406	RELOCATE EXISTING VIDEO ENCODER, SPECIAL	EACH	2								2																				
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2								2																				
X8620050	UNINTERRUPTABLE POWER SUPPLY, GROUND MOUNTED	EACH	1											1																	
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	38	3	1	1	11	1	1	1	5	2	2		1	1	1	1	2	1	1	1	1								
X8803040	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	17	5			12																								
X8803051	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	2	2																											

Rev.

FILE NAME = S:\WP\Design\LP\LED projects\60T85 - LA Co LED - RWA\CAD files\Sheet Files\12-004	USER NAME = pociechal	DESIGNED - DW	REVISED - LP 1/9/13	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 4 OF 5)	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - Lake Co\60T85JDHKE.S004.dgn	REVISED -				2012-040TS	LAKE	60	7
	PLOT SCALE = 40.0000 ' / in.	CHECKED - KMM	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60T85		
	PLOT DATE = 1/9/2013	DATE -	REVISED -				ILLINOIS FED. AID PROJECT			