

February 25, 2013

SUBJECT: FAP Route 397 (IL 83/ Sibley Blvd.) Project HSIP-0397(005) Section 104TS-1(12) Cook County Contract No. 60T92 Item No. 60, March 8, 2013 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Replaced the Schedule of Prices.
- 2. Revised the Table of Contents to the Special Provisions.
- 3. Revised pages 2 & 182-185 of the Special Provisions.
- 4. Revised sheets 1-6 & 8 of the Plans.
- 5. Added sheet 38A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P. E. Acting Engineer of Design and Environment

Seater Dalachbyon DE.

By: Ted B. Walschleger, P. E. Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Mike Renner; Estimates

MS/ks

C-91-500-12 State Job # -

County Name -

Project Number HSIP-0397/005/

Route

FAP 397

Code -31 - -District -

1 - -

COOK--

* REVISED: FEBRUARY 25, 2013

Section Number - 104TS-1 (12)

| ltem | | Unit of | | | | | |
|---------------|-----------------------|---------|-----------|---|------------|---|-------------|
| Number | Pay Item Description | Measure | Quantity | X | Unit Price | = | Total Price |
| XX005431 | LOC UNDERGR UTILITY | EACH | 3.000 | | | | |
| X0324085 | EM VEH P S LSC 20 3C | FOOT | 273.500 | | | | |
| X0327318 | VIDEO DETECT SYS PART | EACH | 1.000 | | | | |
| X6030310 | FR & LIDS ADJUST SPL | EACH | 10.000 | | | | |
| X8570226 | FAC T4 CAB SPL | EACH | 1.000 | | | | |
| X8620200 | UNINTER POWER SUP SPL | EACH | 1.000 | | | | |
| X8710024 | FOCC62.5/125 MM12SM24 | FOOT | 4,516.000 | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1.000 | | | | |
| Z0018500 | DRAINAGE STR CLEANED | EACH | 31.000 | | | | |
| Z0030850 | TEMP INFO SIGNING | SQ FT | 51.400 | | | | |
| Z0033046 | RE-OPTIMIZE SIG SYS 2 | EACH | 1.000 | | | | |
| 20101200 | TREE ROOT PRUNING | EACH | 1.000 | | | | |
| *REV 20201200 | REM & DISP UNS MATL | CU YD | 28.000 | | | | |
| 21101615 | TOPSOIL F & P 4 | SQ YD | 105.500 | | | | |
| *REV 25200110 | SODDING SALT TOLERANT | SQ YD | 105.500 | | | | |

Page 1 2/25/2013

* REVISED: FEBRUARY 25, 2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

Code -31 - -

COOK--

County Name -

District -1 - -

Section Number - 104TS-1 (12)

| | em nber | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|------|------------|----------------------|--------------------|-----------|---|------------|---|-------------|
| | 28000510 | INLET FILTERS | EACH | 9.000 | | | | |
| | 31101200 | SUB GRAN MAT B 4 | SQ YD | 72.000 | | | | |
| *REV | 40600200 | BIT MATLS PR CT | TON | 4.500 | | | | |
| | 40600300 | AGG PR CT | TON | 22.000 | | | | |
| | 40600400 | MIX CR JTS FLANGEWYS | TON | 8.000 | | | | |
| | 40600827 | P LB MM IL-4.75 N50 | TON | 229.000 | | | | |
| | 40600895 | CONSTRUC TEST STRIP | EACH | 1.000 | | | | |
| | 40600982 | HMA SURF REM BUTT JT | SQ YD | 56.500 | | | | |
| | 40603595 | P HMA SC "F" N90 | TON | 543.000 | | | | |
| | 42001300 | PROTECTIVE COAT | SQ YD | 167.000 | | | | |
| | 42400200 | PC CONC SIDEWALK 5 | SQ FT | 950.000 | | | | |
| | 42400800 | DETECTABLE WARNINGS | SQ FT | 196.400 | | | | |
| | 44000159 | HMA SURF REM 2 1/2 | SQ YD | 5,530.000 | | | | |
| | 44000500 | COMB CURB GUTTER REM | FOOT | 200.000 | | | | |
| | 44000600 | SIDEWALK REM | SQ FT | 1,030.000 | | | | |

Page 2 2/25/2013

* REVISED: FEBRUARY 25, 2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

County Name -Code -31 - -

District -1 - -

Section Number - 104TS-1 (12)

COOK--

| | em mber | Pay Item Description | Unit of Measure | | | Unit Price | _ | Total Price |
|------|------------|-----------------------|--------------------|----------|---|------------|---|-------------|
| nui | libei | Fay item Description | weasure | Quantity | X | Unit Frice | = | |
| *ADD | 56400510 | FIRE HYDNT REM & REPL | EACH | 1.000 | | | | |
| | 60300305 | FR & LIDS ADJUST | EACH | 10.000 | | | | |
| | 60603800 | COMB CC&G TB6.12 | FOOT | 50.000 | | | | |
| | 60605000 | COMB CC&G TB6.24 | FOOT | 150.000 | | | | |
| *ADD | 66900200 | NON SPL WASTE DISPOSL | CU YD | 500.000 | | | | |
| *ADD | 66900450 | SPL WASTE PLNS/REPORT | L SUM | 1.000 | | | | |
| *ADD | 66900530 | SOIL DISPOSAL ANALY | EACH | 3.000 | | | | |
| | 67000400 | ENGR FIELD OFFICE A | CAL MO | 6.000 | | | | |
| | 67100100 | MOBILIZATION | L SUM | 1.000 | | | | |
| | 70102620 | TR CONT & PROT 701501 | L SUM | 1.000 | | | | |
| | 70102635 | TR CONT & PROT 701701 | L SUM | 1.000 | | | | |
| | 70102640 | TR CONT & PROT 701801 | L SUM | 1.000 | | | | |
| | 70106800 | CHANGEABLE MESSAGE SN | CAL MO | 2.000 | | | | |
| | 70300100 | SHORT TERM PAVT MKING | FOOT | 850.000 | | | | |
| | 70300210 | TEMP PVT MK LTR & SYM | SQ FT | 103.000 | | | | |

Page 3 2/25/2013

* REVISED: FEBRUARY 25, 2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

Code -31 - -

County Name -

District -1 - -

Section Number - 104TS-1 (12)

COOK--

| ltem Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-----------|---|------------|---|-------------|
| 70300220 | TEMP PVT MK LINE 4 | FOOT | 3,450.000 | | | | |
| 70300240 | TEMP PVT MK LINE 6 | FOOT | 145.000 | | | | |
| 70300260 | TEMP PVT MK LINE 12 | FOOT | 500.000 | | | | |
| 70300280 | TEMP PVT MK LINE 24 | FOOT | 55.000 | | | | |
| 70301000 | WORK ZONE PAVT MK REM | SQ FT | 95.000 | | | | |
| 72000100 | SIGN PANEL T1 | SQ FT | 15.000 | | | | |
| 72000200 | SIGN PANEL T2 | SQ FT | 13.750 | | | | |
| 72400310 | REMOV SIGN PANEL T1 | SQ FT | 8.300 | | | | |
| 78000100 | THPL PVT MK LTR & SYM | SQ FT | 103.000 | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | 3,450.000 | | | | |
| 78000400 | THPL PVT MK LINE 6 | FOOT | 145.000 | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | 500.000 | | | | |
| 78000650 | THPL PVT MK LINE 24 | FOOT | 55.000 | | | | |
| 78100100 | RAISED REFL PAVT MKR | EACH | 60.000 | | | | |
| 78300200 | RAISED REF PVT MK REM | EACH | 30.000 | | | | |

Page 4 2/25/2013

* REVISED: FEBRUARY 25, 2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

County Name -COOK--Code -31 - -

District -1 - -

Section Number - 104TS-1 (12)

| ltem Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-----------|---|------------|---|-------------|
| 80500020 | | EACH | 1.000 | | | | |
| 81028200 | UNDRGRD C GALVS 2 | FOOT | 977.000 | | | | |
| 81028210 | UNDRGRD C GALVS 2 1/2 | FOOT | 104.500 | | | | |
| 81028220 | UNDRGRD C GALVS 3 | FOOT | 78.000 | | | | |
| 81028230 | UNDRGRD C GALVS 3 1/2 | FOOT | 42.000 | | | | |
| 81028240 | UNDRGRD C GALVS 4 | FOOT | 235.000 | | | | |
| 81400100 | HANDHOLE | EACH | 6.000 | | | | |
| 81400200 | HD HANDHOLE | EACH | 2.000 | | | | |
| 81400300 | DBL HANDHOLE | EACH | 1.000 | | | | |
| 85000200 | MAIN EX TR SIG INSTAL | EACH | 2.000 | | | | |
| 86400100 | TRANSCEIVER - FIB OPT | EACH | 1.000 | | | | |
| 87300925 | ELCBL C TRACER 14 1C | FOOT | 4,516.000 | | | | |
| 87301215 | ELCBL C SIGNAL 14 2C | FOOT | 427.000 | | | | |
| 87301225 | ELCBL C SIGNAL 14 3C | FOOT | 728.500 | | | | |
| 87301245 | ELCBL C SIGNAL 14 5C | FOOT | 1,029.500 | | | | |

Page 5 2/25/2013

* REVISED: FEBRUARY 25, 2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

County Name -COOK--Code -31 - -

District -1 - -

Section Number - 104TS-1 (12)

| ltem Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|----------------------|--------------------|-----------|---|------------|---|-------------|
| 87301255 | ELCBL C SIGNAL 14 7C | FOOT | 1,344.500 | | | | |
| 87301305 | ELCBL C LEAD 14 1PR | FOOT | 1,157.500 | | | | |
| 87301805 | ELCBL C SERV 6 2C | FOOT | 35.500 | | | | |
| 87301900 | ELCBL C EGRDC 6 1C | FOOT | 518.000 | | | | |
| 87502490 | TS POST GALVS 15 | EACH | 2.000 | | | | |
| 87502500 | TS POST GALVS 16 | EACH | 2.000 | | | | |
| 87700160 | S MAA & P 24 | EACH | 1.000 | | | | |
| 87700210 | S MAA & P 34 | EACH | 2.000 | | | | |
| 87700220 | S MAA & P 36 | EACH | 1.000 | | | | |
| 87800100 | CONC FDN TY A | FOOT | 16.000 | | | | |
| 87800150 | CONC FDN TY C | FOOT | 4.000 | | | | |
| 87800400 | CONC FDN TY E 30D | FOOT | 10.000 | | | | |
| 87800415 | CONC FDN TY E 36D | FOOT | 33.000 | | | | |
| 87900200 | DRILL EX HANDHOLE | EACH | 1.000 | | | | |
| 88030020 | SH LED 1F 3S MAM | EACH | 6.000 | | | | |

Page 6 2/25/2013

C-91-500-12 State Job # -

Project Number HSIP-0397/005/

Route

FAP 397

Code -31 - -

District -1 - -

County Name -

Section Number - 104TS-1 (12)

COOK--

* REVISED: FEBRUARY 25, 2013

| ltem Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-----------|---|------------|---|-------------|
| 88030070 | SH LED 1F 4S BM | EACH | 2.000 | | | | |
| 88030080 | SH LED 1F 4S MAM | EACH | 2.000 | | | | |
| 88030100 | SH LED 1F 5S BM | EACH | 2.000 | | | | |
| 88030110 | SH LED 1F 5S MAM | EACH | 2.000 | | | | |
| 88102717 | PED SH LED 1F BM CDT | EACH | 4.000 | | | | |
| 88200210 | TS BACKPLATE LOU ALUM | EACH | 10.000 | | | | |
| 88500100 | INDUCTIVE LOOP DETECT | EACH | 7.000 | | | | |
| 88600100 | DET LOOP T1 | FOOT | 515.000 | | | | |
| 88700200 | LIGHT DETECTOR | EACH | 2.000 | | | | |
| 88700300 | LIGHT DETECTOR AMP | EACH | 1.000 | | | | |
| 88800100 | PED PUSH-BUTTON | EACH | 4.000 | | | | |
| 89502300 | REM ELCBL FR CON | FOOT | 8,832.000 | | | | |
| 89502380 | REMOV EX HANDHOLE | EACH | 1.000 | | | | |

Page 7 2/25/2013

FAP 397 (IL 83/Sibley Blvd.) Project HSIP-0397(005) Section 104TS-1 (12) Cook County Contract 60T92

TABLE OF CONTENTS

| LOCATION OF PROJECT | .1 |
|--|----|
| DESCRIPTION OF PROJECT | .1 |
| MAINTENANCE OF ROADWAYS | .1 |
| STATUS OF UTILITIES TO BE ADJUSTED | .2 |
| PUBLIC CONVENIENCE AND SAFETY (DIST 1) | .3 |
| HMA MIXTURE DESIGN REQUIREMENTS (D-1) | |
| GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1) | .7 |
| FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1) | .9 |
| FRICTION SURFACE AGGREGATE (D1) | .9 |
| HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDE | ER |
| | 12 |
| HOT MIX ASPHALT MIXTURE IL-4.75 (DIST 1) | 13 |
| RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1) | 15 |
| CLEANING EXISTING DRAINAGE STRUCTURES | 26 |
| DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1) | 27 |
| ADJUSTMENTS AND RECONSTRUCTIONS | |
| TRAFFIC CONTROL PLAN | 29 |
| TEMPORARY INFORMATION SIGNING | 30 |
| ELECTRIC SERVICE INSTALLATION | 31 |
| UNIT DUCT | 32 |
| TRAFFIC SIGNAL SPECIFICATIONS | 33 |
| FULL-ACTUATED CONTROLLER AND CABINET (SPECIAL) | 93 |
| EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C | |
| VIDEO DETECTION SYSTEM, PARTIAL | 94 |
| CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) | 96 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) | 99 |
| GRANULAR MATERIALS (BDE)1 | 08 |
| HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) | 09 |
| PAVEMENT MARKING REMOVAL (BDE)1 | 10 |
| PAYMENTS TO SUBCONTRACTORS (BDE)1 | 10 |
| PLACING AND CONSOLIDATING CONCRETE (BDE)1 | 12 |
| PORTLAND CEMENT CONCRETE (BDE)1 | 14 |
| QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE) | 64 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES | 82 |

| REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE) | 186 |
|--|-----|
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) | |
| TRACKING THE USE OF PESTICIDES (BDE) | |
| TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) | |
| UTILITY COORDINATION AND CONFLICTS (BDE) | |
| WARM MIX ASPHALT (BDE) | 193 |
| WEEKLY DBE TRUCKING REPORTS (BDE) | |
| WORKING DAYS (BDE) | 201 |
| STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) | 201 |

FAP 397 (IL 83/Sibley Blvd.) Project HSIP-0397(005) Section 104TS-1 (12) Cook County Contract 60T92

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

STATUS OF UTILITIES TO BE ADJUSTED

Effective: January 30, 1987 Revised: January 24, 2013

Utilities companies involved in this project have provided the following estimated durations:

| NAME OF UTILITY | ТҮРЕ | LOCATION | Estimated Duration of Time for the Completion of Relocation or Adjustments | | | | |
|-----------------|-------|---|--|--|--|--|--|
| ComEd | Power | Power pole to be relocated on North side of IL 83, east of Wallace Street | Will require approximately (2) weeks 15 working days | | | | |
| | | | | | | | |

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

In accordance with 605 ILCS 5/9-113 of the Illinois Compiled Statutes, utility companies have 90 days to complete the relocation of their facilities after receipt of written notice from the Department. The 90-day written notice will be sent to the utility companies after the following occurs:

- 1) Proposed right of way is clear for contract award.
- 2) Final plans have been sent to and received by the utility company.
- 3) Utility permit is received by the Department and the Department is ready to issue said permit.
- 4) If a permit has not been submitted, a 15 day letter is sent to the utility company notifying them they have 15 days to provide their permit application. After allowing 15 days for submission of the permit the 90 day notice is sent to the utility company.
- 5) Any time within the 90 day relocation period the utility company may request a waiver for additional time to complete their relocation. The Department has 10 days to review and respond to a waiver request.

FAP 397 (IL 83/Sibley Blvd.) Project HSIP-0397(005) Section 104TS-1 (12) Cook County Contract 60T92

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Revise Article 669.01 of the Standard Specifications to read:

"669.01 Description. This work shall consist of the transportation and proper disposal of contaminated soil and water. This work shall also consist of the removal, transportation, and proper disposal of underground storage tanks (UST), their content and associated underground piping to the point where the piping is above the ground, including determining the content types and estimated quantities."

Revise Article 669.08 of the Standard Specifications to read:

"669.08 Contaminated Soil and/or Groundwater Monitoring. The Contractor shall hire a qualified environmental firm to monitor the area containing the regulated substances. The affected area shall be monitored with a photoionization detector (PID) utilizing a lamp of 10.6eV or greater or a flame ionization detector (FID). Any field screen reading on the PID or FID in excess of background levels indicates the potential presence of contaminated material requiring handling as a non-special waste, special waste, or hazardous waste. No excavated soils can be taken to a clean construction and demolition debris (CCDD) facility or an uncontaminated soil fill operation with detectable PID or FID meter readings that are above background. The PID or FID meter shall be calibrated on-site and background level readings taken and recorded daily. All testing shall be done by a qualified engineer/technician. Such testing and monitoring shall be included in the work. The Contractor shall identify the exact limits of removal of non-special waste, special waste, or hazardous waste. All limits shall be approved by the Engineer prior to excavation. The Contractor shall take all necessary precautions.

Based upon the land use history of the subject property and/or PID or FID readings indicating contamination, a soil or groundwater sample shall be taken from the same location and submitted to an approved laboratory. Soil or groundwater samples shall be analyzed for the contaminants of concern, including pH, based on the property's land use history or the parameters listed in the maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605. The analytical results shall serve to document the level of soil contamination. Soil and groundwater samples may be required at the discretion of the Engineer to verify the level of soil and groundwater contamination.

Samples shall be grab samples (not combined with other locations). The samples shall be taken with decontaminated or disposable instruments. The samples shall be placed in sealed containers and transported in an insulated container to the laboratory. The container shall maintain a temperature of 39 °F (4 °C). All samples shall be clearly labeled. The labels shall indicate the sample number, date sampled, location and elevation, and any other observations.

The laboratory shall use analytical methods which are able to meet the lowest appropriate practical quantitation limits (PQL) or estimated quantitation limit (EQL) specified in "Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods", EPA Publication No. SW-846 and "Methods for the Determination of Organic Compounds in Drinking Water", EPA, EMSL, EPA-600/4-88/039. For parameters where the specified cleanup objective is below the acceptable detection limit (ADL), the ADL shall serve as the cleanup objective. For other parameters the ADL shall be equal to or below the specified cleanup objective."

Replace the first two paragraphs of Article 669.09 of the Standard Specifications with the following:

"669.09 Contaminated Soil and/or Groundwater Management and Disposal. The management and disposal of contaminated soil and/or groundwater shall be according to the following:

- (a) Soil Analytical Results Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels exceed the most stringent maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605, the soil shall be managed as follows:
 - (1) When analytical results indicate chemical constituents exceed the most stringent MAC but they are still considered within area background levels by the Engineer, the excavated soil can be utilized within the construction limits as fill, when suitable. Such soil excavated for storm sewers can be placed back into the excavated trench as backfill, when suitable, unless trench backfill is specified. If the soils cannot be utilized within the construction limits, they shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
 - (2) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for a Metropolitan Statistical Area (MSA) County, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
 - (3) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, or the MAC within the Chicago corporate limits, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago or within the Chicago corporate limits provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
 - (4) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of offsite as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago provided the pH of the soil is within the range of 6.25 -9.0, inclusive.
 - (5) When the Engineer determines soil cannot be managed according to Articles 669.09(a)(1) through (a)(4) above, the soil shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
- (b) Soil Analytical Results Do Not Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels do not exceed the most stringent MAC but the pH of the soil is less than 6.25 or greater than 9.0, the excavated soil can be utilized within the construction limits or managed and disposed of off-site as "uncontaminated soil" according to Article 202.03. However the excavated soil cannot be taken to a CCDD facility or an uncontaminated soil fill operation.
- (c) Groundwater. When groundwater analytical results indicate the detected levels are above Appendix B, Table E of 35 Illinois Administrative Code 742, the most stringent Tier 1 Groundwater Remediation Objectives for Groundwater Component of the Groundwater Ingestion Route for Class 1 groundwater, the groundwater shall be managed off-site as a special waste.

All groundwater encountered within lateral trenches may be managed within the trench and allowed to infiltrate back into the ground. If the groundwater cannot be managed within the trench it must be removed as a special or hazardous waste. The Contractor is prohibited from managing groundwater within the trench by discharging it through any existing or new storm sewer. The Contractor shall install backfill plugs within the area of groundwater contamination.

One backfill plug shall be placed down gradient to the area of groundwater contamination. Backfill plugs shall be installed at intervals not to exceed 50 ft (15 m). Backfill plugs are to be 4 ft (1.2 m) long, measured parallel to the trench, full trench width and depth. Backfill plugs shall not have any fine aggregate bedding or backfill, but shall be entirely cohesive soil or any class of concrete. The Contractor shall provide test data that the material has a permeability of less than 10^{-7} cm/sec according to ASTM D 5084, Method A or per another test method approved by the Engineer."

Revise Article 669.14 of the Standard Specifications to read:

"669.14 Final Environmental Construction Report. At the end of the project, the Contractor will prepare and submit three copies of the Environmental Construction Report on the activities conducted during the life of the project, one copy shall be submitted to the Resident Engineer, one copy shall be submitted to the District's Environmental Studies Unit, and one copy shall be submitted with an electronic copy in Adode.pdf format to the Geologic and Waste Assessment Unit, Bureau of Design and Environment, IDOT, 2300 South Dirksen Parkway, Springfield, Illinois 62764. The technical report shall include all pertinent information regarding the project including, but not limited to:

- (a) Measures taken to identify, monitor, handle, and dispose of soil or groundwater containing regulated substances, to prevent further migration of regulated substances, and to protect workers,
- (b) Cost of identifying, monitoring, handling, and disposing of soil or groundwater containing regulated substances, the cost of preventing further migration of regulated substances, and the cost for worker protection from the regulated substances. All cost should be in the format of the contract pay items listed in the contract plans (identified by the preliminary environmental site investigation (PESA) site number),
- (c) Plan sheets showing the areas containing the regulated substances,
- (d) Field sampling and testing results used to identify the nature and extent of the regulated substances,
- (e) Waste manifests (identified by the preliminary environmental site investigation (PESA) site number) for special or hazardous waste disposal, and
- (f) Landfill tickets (identified by the preliminary environmental site investigation (PESA) site number) for non-special waste disposal."

Revise the second paragraph of Article 669.16 of the Standard Specifications to read:

"The transportation and disposal of soil and other materials from an excavation determined to be contaminated will be paid for at the contract unit price per cubic yard (cubic meter) for NON-SPECIAL WASTE DISPOSAL, SPECIAL WASTE DISPOSAL, or HAZARDOUS WASTE DISPOSAL."

<u>Qualifications</u>. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

<u>General.</u> This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either "uncontaminated soil" or non-special waste. <u>This</u> work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. <u>Phase I Preliminary Engineering information</u> is available through the District's Environmental Studies Unit. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:

- Station 17+35 to Station 20+00 0 to 50 feet LT (Strip Mall, PESA Site 2118-2, 369 East 147th Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.
- Station 20+00 to Station 20+80 0 to 50 feet LT (Hi-Hard Corporation, PESA Site 2118-3, 379 East 147th Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.
- Station 20+80 to Station 21+40 0 to 50 feet LT (Vacant Building, PESA Site 2118-6, 346 West 147th Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.
- Station 21+40 to Station 22+30 0 to 50 feet LT (Holiday Car Wash, PESA Site 2118-7, 340 West 147th Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.
- Station 17+35 to Station 20+80 0 to 50 feet RT (Vacant Lot, PESA Site 2118-4, 400 East 147th Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.
- Station 20+80 to Station 24+00 0 to 50 feet RT (CEDA Head Start Program, PESA Site 2118-8, 14701 Wallace Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: PNAs and Metals.