

**SUMMARY OF QUANTITIES**

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	40	40				
20101000	TEMPORARY FENCE	FOOT	2,400	2,400				
20101200	TREE ROOT PRUNING	EACH	53	53				
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	28	28				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25				
20200100	EARTH EXCAVATION	CU YD	27,273	27,273				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12,664	12,664				
20400800	FURNISHED EXCAVATION	CU YD	303	303				
20800150	TRENCH BACKFILL	CU YD	2,692	2,692				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	30,205	30,205				
25000210	SEEDING, CLASS 2A	ACRE	2.75	2.75				
25000300	SEEDING, CLASS 3	ACRE	3.00	3.00				
25000312	SEEDING, CLASS 4A	ACRE	0.50	0.50				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	522	522				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	522	522				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	522	522				
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	23,695	23,695				
25200110	SODDING, SALT TOLERANT	SO YD	6,510	6,510				
25200200	SUPPLEMENTAL WATERING	UNIT	325	325				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	624	624				
28000305	TEMPORARY DITCH CHECKS	FOOT	950	950				
28000315	AGGREGATE DITCH CHECKS	TON	5	5				
28000400	PERIMETER EROSION BARRIER	FOOT	15,745	15,745				
28000500	INLET AND PIPE PROTECTION	EACH	18	18				
28000510	INLET FILTERS	EACH	46	46				
28100105	STONE RIPRAP, CLASS A3	SO YD	37	37				
28100107	STONE RIPRAP, CLASS A4	SO YD	438	438				
28200200	FILTER FABRIC	SO YD	719	719				
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	4,818	4,818				
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	21,585	21,585				
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	1,395	1,395				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	157	157				
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	2,810	2,810				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,245	1,245				

\* SPECIALTY ITEM

COMPANY NAME: HRGreen.com  
 PROJECT CONTACT: jettone  
 CLIENT: MCHENRY COUNTY  
 DATE PLOTTED: 12/20/2012 9:56:59 AM  
 DRAWN: JPA  
 FILE NAME: 090622-sum.dgn  
 PLOT SCALE: N.T.S.  
 PLOT DRIVER: pdf2dwg.exe  
 PEN TABLE: standard.ctb



USER NAME: jettone	DESIGNED: JRM	REVISED:
FILE NAME: 090622-sum.dgn	DRAWN: JPA	REVISED:
PLOT SCALE: N.T.S.	CHECKED: TH	REVISED:
PLOT DATE: 12/20/2012	DATE: 12/20/12	REVISED:

**MCHENRY COUNTY  
DIVISION OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 1 OF 8 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00314-00-WR	MCHENRY	187	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63515	