

SUMMARY OF QUANTITIES (CONTD.)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,434	4,434				
40600300	AGGREGATE (PRIME COAT)	TON	133	133				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	117	117				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,965	2,965				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,395	2,395				
40701946	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/4"	SO YD	11,691	11,691				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	49	49				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	48	48				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	10,277	10,277				
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	80	80				
42400800	DETECTABLE WARNINGS	SO FT	269	269				
44000100	PAVEMENT REMOVAL	SO YD	11,329	11,329				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1,758	1,758				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,072	4,072				
44000600	SIDEWALK REMOVAL	SO FT	235	235				
44004000	PAVED DITCH REMOVAL	FOOT	979	979				
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SO YD	110	110				
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SO YD	665	665				
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SO YD	110	110				
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SO YD	110	110				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,206	6,206				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	1,831	1,831				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	4,272	4,272				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1				
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1				
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4				
50105220	PIPE CULVERT REMOVAL	FOOT	765	765				
50200100	STRUCTURE EXCAVATION	CU YD	740		740			
50300225	CONCRETE STRUCTURES	CU YD	220		220			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	86,870		86,870			

* SPECIALTY ITEM

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: jettone
 CLIENT: MCHENRY COUNTY
 DATE PLOTTED: 12/20/2012 09:46:01 AM
 FILE NAME: 080822-sum.dgn
 PLOT NUMBER: 080822-sum.dgn
 PER: JBL



USER NAME = jettone	DESIGNED - JRM	REVISED -
FILE NAME = 080822-sum.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 12/20/2012	DATE - 12/20/12	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 8 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00314-00-WR	MCHENRY	187	5
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 63515	