

SUMMARY OF QUANTITIES (CONTD.)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	732	732				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	185		185			
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2		2			
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	5	5				
60200905	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	10	10				
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	9	9				
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5				
60204805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60205312	CATCH BASINS, TYPE A, 6'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	3	3				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14	14				
60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6				
60224020	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60224443	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60224461	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1				
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	6	6				
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	16	16				
60402210	GRATES, TYPE 8	EACH	3	3				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	15	15				
60600605	CONCRETE CURB, TYPE B	FOOT	108	108				
60602500	CONCRETE GUTTER, TYPE A	FOOT	3,016	3,016				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	5,610	5,610				
60616110	PAVED DITCH, TYPE A-30	FOOT	325	325				
60616800	PAVED DITCH, TYPE B-15	FOOT	120	120				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	450.0	450.0				
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	687.5	687.5				
* 63000009	STEEL PLATE BEAM GUARDRAIL, TYPE B, 9 FOOT POSTS	FOOT	100.0	100.0				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	10				

* SPECIALTY ITEM

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 DATE PLOTTED: 1/3/2013 9:27:37 AM
 FILE NAME: 080622-sum.dgn
 PLOT NAME: 080622-sum.dgn
 PLOT TABLES: 080622-sum.dgn



USER NAME = spornal	DESIGNED - JRM	REVISED -
FILE NAME = 080622-sum.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 1/3/2013	DATE - 1/3/13	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 4 OF 8 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00314-00-WR	MCHENRY	187	7
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 63515