


SUMMARY OF QUANTITIES (CONTD.)

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	MCDOT			JOHNSBURG	
				ROADWAY 80% FEDERAL 20% LOCAL 0004	RETAINING WALL 80% FEDERAL 20% LOCAL 0040	SIGNALS/LIGHTING 80% FEDERAL 20% LOCAL 0021	ITEP 80% FEDERAL 20% LOCAL 0031	VILLAGE OF JOHNSBURG 100% LOCAL 0043
63200310	GUARDRAIL REMOVAL	FOOT	1,460	1,460				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	220	220				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	48	48				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5,600	5,600				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26,900	26,900				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	160	160				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3,650	3,650				
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	100	100				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,300	3,300				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,625.0	1,625.0				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	837.5	837.5				
70600240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2				
70600340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	1	1				
72000100	SIGN PANEL - TYPE 1	SQ FT	598	580		18		
72000200	SIGN PANEL - TYPE 2	SQ FT	97	45		52		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	730	730				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32,894	32,894				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,582	2,582				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,093	1,093				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	284	284				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24				
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	190	190				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,670	1,670				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	70	70				
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2				2	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1				1	
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			2		
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	457			41	416	
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	146			146		
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	156			156		
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,000			739	261	

* SPECIALTY ITEM

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: 1/3/2013 9:27:41 AM
 DATE PLOTTED: 080622-sum.dgn
 FILE NAME: 080622-sum.dgn
 PLOT DRIVER: pdf_writer
 PEN TABLE: standard-trans.tbl



USER NAME = sperral	DESIGNED - JRM	REVISED -
FILE NAME = 080622-sum.dgn	DRAWN - JPA	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TH	REVISED -
PLOT DATE = 1/3/2013	DATE - 1/3/13	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 5 OF 8 SHEETS STA. TO STA.

F.A.U. RTE. 168	SECTION 05-00314-00-WR	COUNTY MCHENRY	TOTAL SHEETS 187	SHEET NO. 8
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 63515		