

**STORM SEWER SCHEDULE**

PIPE NO.	FROM STRUCT.	TO STRUCT.	STORM SEWER, CLASS A											4' X 2' BOX	2' X 2' BOX	TYPE	SLOPE (%)
			12"	15"	18"	24"	27"	30"	36"	42"	48"	54"					
<b>JOHNSBURG ROAD</b>																	
2	1	3													95		0.11%
4	3	7													45		0.22%
6	5	7	17														2 0.88%
7	7	8													22		0.17%
8	8	9													37		0.27%
10	9	11													9		0.22%
11	END SECTION	END SECTION													65		0.37%
14	13	15	21														2 0.48%
16	15	19			104												2 0.38%
18	17	19	8														1 1.25%
20	19	21			196												2 0.47%
22	21	25			132												2 1.60%
24	23	25	13														2 0.77%
26	25	27				113											2 0.25%
28	27	29					41										2 0.24%
30	29	31					39										2 0.23%
42	41	43	114														2 4.11%
44	43	47	135														2 1.93%
48	47	21	6														2 1.67%
52	51	54					27										3 0.41%
53	54	53					68										3 0.03%
54	34	35			89												2 1.24%
55	33	34			147												1 1.57%
56	32	33			147												2 0.96%
57	58	32			147												2 1.00%
58	35	54	8														2 2.50%
59	55	34	4														2 2.50%
60	56	33	4														2 2.50%
61	57	32	4														1 2.50%
62	61	63	34														1 0.59%
64	65	63	9														2 1.11%
66	65	67	147														2 0.71%
68	67	69	147														2 1.42%
70	69	71	97														2 2.58%
72	71	73		122													2 2.87%
74	73	133		73													2 2.25%
79	147	79	62														2 3.13%
80	79	81			97												2 1.85%
92	91	93	34														1 0.53%
94	93	67	9														1 1.11%
102	101	103	34														1 0.59%
104	103	69	9														1 1.11%
112	111	113	34														1 0.44%
114	113	71	9														1 1.11%
122	121	123	37														1 0.54%
124	123	73	9														1 1.11%
132	131	133	34														1 0.88%
134	75	133	2														1 2.50%
135	133	77			97												2 3.07%
142	141	77	37														1 0.68%
144	143	77	4														1 2.50%
145	77	148			71												2 1.38%
152	151	148	40														1 0.42%
154	148	79	10														1 1.00%
162	163	161					191										1 0.40%

PIPE NO.	FROM STRUCT.	TO STRUCT.	STORM SEWER, CLASS A											4' X 2' BOX	2' X 2' BOX	TYPE	SLOPE (%)
			12"	15"	18"	24"	27"	30"	36"	42"	48"	54"					
164	165	163	7														1 1.29%
166	167	163			47												1 0.21%
182	181	183	95														1 3.31%
184	183	185	199														2 0.59%
186	185	187		222													2 0.67%
188	187	189			25												3 1.12%
192	191	193	36														1 0.58%
210	211	209	12														2 2.08%
212	213	211	9														2 2.78%
222	223	221										6					3 3.00%
224	224	223										220					3 0.10%
225	227	224										65					3 0.09%
226	225	252	51														1 0.35%
228	229	227											46				3 0.15%
230	231	229											95				3 0.05%
232	233	231											225				3 0.11%
234	235	233										141					2 0.09%
236	237	235					31										2 0.45%
238	239	237			216												2 1.45%
240	241	239	31														1 0.65%
262	261	231	41														1 0.49%
272	272	273	17														1 0.59%
274	273	233	39														1 0.51%
282	285	281	31														1 0.48%
283	286	285	9														1 1.11%
286	281	235	30														1 0.67%
292	291	237	10														2 1.00%

PIPE NO.	FROM STRUCT.	TO STRUCT.	STORM SEWER, CLASS A											4' X 2' BOX	2' X 2' BOX	TYPE	SLOPE (%)
			12"	15"	18"	24"	27"	30"	36"	42"	48"	54"					
<b>SPRING GROVE ROAD</b>																	
602	601	603	29														2 0.69%
604	603	605	7														2 1.14%
606	605	607	197														2 1.43%
608	607	609	96														1 0.84%
610	609	611										125					2 0.26%
616	625	631										266					2 1.04%
622	621	623	31														1 0.65%
624	623	607	7														1 1.43%
632	631	609											59				2 1.75%

<b>RIVERSIDE DRIVE</b>																	
702	701	703	46														2 0.79%
712	711	713	35														1 0.61%

12/19/2012 3:26:02 PM  
 090622-ssch.dgn  
 p:\p\dw-no-10\velofrc\p  
 standard-frames.tbl



HRGreen.com  
 Illinois Professional Design Firm  
 #194-011322

USER NAME = jettone  
 FILE NAME = 090622-ssch.dgn  
 PLOT SCALE = N.T.S.  
 PLOT DATE = 12/19/2012

DESIGNED - JRM  
 DRAWN - JPA  
 CHECKED - TH  
 DATE - 12/19/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**MCHENRY COUNTY  
 DIVISION OF TRANSPORTATION**

**DRAINAGE SCHEDULE OF QUANTITIES  
 JOHNSBURG ROAD**

SCALE: N.T.S. SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
168	05-00314-00-WR	MCHENRY	187	60
CONTRACT NO.			63515	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				