

**SUMMARY OF QUANTITIES**

PAY ITEM	ITEM	UNIT	TOTAL QUANTITY	STP/STU FUNDS	
				70% STATE 30% LOCAL	70% STATE 30% LOCAL
				0004 RECONSTRUCTION, NO CAPACITY ADDED	0042 TRAINEEES
				URBAN	URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	480	480	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1015	1015	
20101100	TREE TRUNK PROTECTION	EACH	5	5	
20200100	EARTH EXCAVATION	CU YD	2200	2200	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	580	580	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	580	580	
20800150	TRENCH BACKFILL	CU YD	680	680	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1750	1750	
21101015	TOPSOIL FURNISH AND PLACE 4"	SQ YD	4735	4735	
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	75	75	
25100105	MULCH, METHOD 1	ACRE	1	1	
25200110	SODDING, SALT TOLERANT	SQ YD	4735	4735	
25200200	SUPPLEMENTAL WATERING	UNIT	60	60	
28000250	TEMPORARY EROSION CONTROL, SEEDING	POUND	100	100	
28000510	INLET FILTERS	EACH	20	20	
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	5240	5240	
40500100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5905	5905	
40600300	AGGREGATE (PRIME COAT)	TON	30	30	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	10	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, NS0	TON	2210	2210	
40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NS0	TON	1105	1105	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1815	1815	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31300	31300	
42400800	DETECTABLE WARNINGS	SQ FT	240	240	
44000100	PAVEMENT REMOVAL	SQ YD	8875	8875	
44000150	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	200	200	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1760	1760	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6440	6440	
44000600	SIDEWALK REMOVAL	SQ FT	28780	28780	

PAY ITEM	ITEM	UNIT	TOTAL QUANTITY	STP/STU FUNDS	
				70% STATE 30% LOCAL	70% STATE 30% LOCAL
				0004 RECONSTRUCTION, NO CAPACITY ADDED	0042 TRAINEEES
				URBAN	URBAN
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	11	11	
55100500	STORM SEWER REMOVAL 12"	FOOT	30	30	
550A0060	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1145	1145	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	315	315	
550A0080	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	145	145	
56300200	ADJUSTING SANITARY SEWERS, OVER 8-INCH DIAMETER	FOOT	20	20	
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	12	12	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	11	11	
60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	4	4	
60222000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	5	5	
60236600	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	20	20	
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-B 12"	FOOT	6355	6355	
67100100	MOBILIZATION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	
72000100	SIGN PANEL - TYPE 1	SQ FT	150	150	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	240	240	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3720	3720	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	505	505	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	110	110	
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3000	3000	
A2000120	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	30	30	
A2004420	TREE, GINKGO BILOBA (GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	15	15	
A2004720	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	11	11	
A2006620	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	19	19	
A2008120	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16	16	
X0327301	RELOCATE EXISTING MAILBOX	EACH	2	2	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	95	95	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
Z0004610	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	125	125	
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	200	200	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0076600	TRAINEEES	HOUR	500		500
Z0076604	TRAINEEES TRAINING PROGRAM GRADUATE	HOUR	500		500
X008314	CURED-IN-PLACE PIPE LINER, 24" X 42"	FOOT	182	182	
Z0300106	AGGREGATE SUBGRADE IMPROVEMENT 8"	SQ YD	11600	11600	

- INDICATES SPECIAL PROVISION  
\* INDICATES SPECIALTY ITEM